



## UCH COMPRESSION PROJECT



**Design Engineering, Procurement (Supply), Construction, Installation/Erection, Pre-Commissioning, Commissioning & Start-up (including performance testing and Reliability Guarantee Test) of Compression System at UCH Compression Project**  
**Tender Enquiry No. PROC-FC/CB/PROJ/UCH(COM)-4462/2019**

### PRE-BID CLARIFICATION # 39

Item No.	Tender Document Reference	Query	Response
1	0221-GS-9510-3 (Spec for Centrifugal Compressors)	There are the following uncomplianced description about the lube oil cooler in the document: 3.1.4.2 Lube oil air cooled exchanger (2x50%) sized for maximum cooling at highest ambient temperature. 8.2.3 h)..... Lube oil cooler shall be supplied with 3 x 50 % (2 working 1 stand-by) fans, steel support structure, ladder etc. Which one should we follow?	Bidder to follow Clause # 3.1.4.2 which states that ; "Lube oil air cooled exchanger (2x50%) sized for maximum cooling at highest ambient temperature."