



WEB TENDER DOCUMENTS

**TENDER ENQUIRY NO
SP-4/WT/10038472/BOUNDARY WALL/2025/06**

**FOR
CONCRETE BOUNDARY WALL SIZE
8FT HEIGHT X 1750 RFT ALONG WITH COLUMN 10 FT**

BASE CAMP IN KOHAT NORTH 3D PROJECT

**PARTY CHIEF
SEISMIC PARTY NO.4
(LOCAL PURCHASING)**

OIL & GAS DEVELOPMENT COMPANY LIMITED

BID SUBMISSION DATE: 15th September 2025

OGDCL SALES TAX REGISTRATION

NO. 07-02-2802-001-55

INVITATION FOR BIDS

BIDDING DOCUMENT

TENDER ENQUIRY NO:
SP4/WT/10038472/BOUNDARYWALL/2025/06)

Annexure (A)

Schedule of Requirement
(Web Tender #SP4/WT/10038472/ BOUNDARYWALL/2025/06)

Format of submission of bid:

Sr.	Description	Reference #	Rate	Total Rate Included of all Taxes
1	As per attached list			

WEB TENDER FOR PURCHASE OF CONCRETE BOUNDARY WALL FOR BASE CAMP AT SEISMIC PARTY NO.4

Sr.	Item Description and Specification	Quantity	Unit
1	<p>CONCRETE BOUNDARY WALL SIZE **8 FT HEIGHT ALONG WITH COLUMN 10 FT**</p> <ul style="list-style-type: none"> ✓ Plank Dimensions Reinforced Cement Concrete (RCC) boundary wall of 8 Running Feet (Rft) in length, 1 Foot (Ft) in width, and 2 Inches (In) in thickness. ✓ Column Dimensions <ul style="list-style-type: none"> ○ RCC columns of 10 Ft height at suitable intervals, ○ embedded properly in foundation for structural stability. ✓ Concrete Grade <ul style="list-style-type: none"> ○ Minimum Grade M-20 (1:1.5:3 mix ratio) or as ○ per Pakistan Standard Specifications ○ for both wall and columns. ✓ Reinforcement <ul style="list-style-type: none"> ○ High-strength deformed steel bars (Grade 60) ○ used in columns and wall. ○ Minimum 4 bars of 12mm dia for columns, ○ tied with 8mm stirrups @ 6" c/c. ✓ Foundation <ul style="list-style-type: none"> ○ Column foundation depth 2.5–3 Ft ○ with a concrete footing base of 1.5 Ft x 1.5 Ft. ✓ Formwork & Curing <ul style="list-style-type: none"> ○ Proper shuttering and formwork to ○ Ensure smooth finish. ○ Minimum curing period: 7–10 days ○ for wall and columns. ✓ Plaster/Finishing <ul style="list-style-type: none"> ○ Both sides of the wall to be finished with ○ 1:4 cement-sand plaster, ½ Inch thick. ○ External face may be painted/treated with ○ Weather-resistant coating. 	1750	RFT

TERMS AND CONDITION

1. The supplier should have minimum of 05 years of past experience in Supplies.
2. Completion period for Supplies is Two Weeks from the date of issuance of Purchase order.
3. Bidding Procedure: Single Stage, Two envelope (**Technical and Financial bids may be submitted in Two Envelopes**)
4. The pay order / demand draft of **Rs 60,000** (Rupees Sixty Thousand only) in favor of Oil & Gas Development Company Limited, as Security deposit /Performance bond must be enclosed with the quotation. Deposit of successful bidder will be Retained and Returned /Refunded after the completion of job. Rest of the bid bonds of Unsuccessful Bidders will be Released.
5. Payment will be made through Online Payment and be released when once successful Completion of Material Supply at site is completed. OGDCL has the right to Reject if Inspection results Found unsatisfactory.
6. Three Months Any type of Damage Warranty Must be in Written Form.
7. Commercial series (Professional)
8. Any damaged found during Inspection will have to be Settled by the Supplier without any extra charges.
9. Supplier to provide all necessary documents like FBR Submitted Status **Annex-C (Tax), Professional Tax Certificate etc. with invoice.**
10. Material will be delivered at **Seismic Party No. 4 Camp Location** the delivery charges to be borne by the Supplier / Bidder.
11. Bidder should submit complete/clean acceptance of **OGDCL TOR.**
12. Any required technical clarification/details regarding Job mentioned above must be cleared before submission of bid. No change in substance of bid will be entertained after bid submission date.
13. OGDCL reserves the right to annul the case without assigning any reason thereof.
14. **Bid Prices should be Inclusive of All Applicable Taxes.**
15. Bid will be opened at Base camp SP-04 Near Ali Zai Base Camp Near Kaccha Pakka 16 km from Kohat City District Kohat KPK.
16. Any information regarding Tender may be obtained from Admin Office via Phone, Email or Base Camp on below address.
17. Seismic Party No.4 (SP4), OGDCL, Near Ali Zai District Kohat KPK
18. **Phone No:051-9244343**
19. **Email: partychiefsp4@ogdcl.com**