

Clarification

Subject: Tender Enquiry No.: PROC-FB/CB/PE&FD-5153/2021

The clarifications are addressed below regarding the subjected tender.

N o.	Section	Requirement of Specification	Clarification	Client Reply
1	7.2.10	Length of cut back: 150mm Coating shall be beveled at 30°	Length of cut back shall be a range, we suggest the length of cut back: 150mm (-20mm / +0) The coating shall be beveled below 30° according to Clause 7.3.5 in DIN 30670-2013	The length of cut back shall be as per TOR/SPECS Table-2 which allows 150±20 mm. Bidder to follow clause 7.3.5 of DIN 30670.
2	7.3.2	The polyethylene topcoat shall have Min. thickness of 3000 μ m	The polyethylene topcoat shall have Min. thickness of 2000 μ m in Clause 1.1.1 of Specification.	Bidder to follow the clause 1.1.1 and Table clause 6.3.1
3	8.1.4.3 8.1.4.4 Table-1	The Max. coating system thickness shall be 3.0mm Any individual reading less than 3.0mm shall be rejected for coated pipe. Coating Thickness: FBE+AD+PE: ≥3.05mm	The thickness of FBE shall be 300 μ m to 400 μ m; the thickness of AD shall be 300 μ m to 400 μ m; and the polyethylene topcoat shall have Min. thickness of 2000 μ m in Clause 1.1.1 of Specification. So the total coating thickness of 3LPE shall be Min. 2.6mm.	Please follow clause 6.1 of Table.
4	Table-2	Cut backs: Bevel 45°	The coating shall be beveled below 30° according to Clause 7.3.5 in DIN 30670-2013	Bidder to follow clause 7.3.5 of DIN 30670.
5	“Delivery allowance of the (+0/- 100 meters) for required pipeline as per SOR can be allowed. However, payment will be made as per actual quantity of pipeline supplied but not more than the SOR quantities.”			