08-03-2022

Revision of Specifications against TE/89/QP-MECH/2022 Dated: 05-02-2022

Hiring of Contractor Services for Repair of U-Stamp Vessel V-2003 Condensate Water Separator as per recommendation by M/s Velosi (Services & Material inclusive)

Following points of Document (Annexure- A) Schedule of Requirement have been revised as below.

Sr #	<u>Previously</u>	<u>Now</u>
4	FLANGES WNRF NPS 3" X 150# SCH 160, MATERIAL A-105 <mark>NACE</mark> , QTY 04 NOS	FLANGES WNRF NPS 3" X 150# SCH 160, MATERIAL A-105, QTY 04 NOS
5	3" PIPE FOR NOZZLES A-106 GR-B SCH XXS NACE	3" PIPE FOR NOZZLES A-106 GR-B SCH 160
11	ROLLING OF INSERT PLATE AS PER ORIGINAL CONSTRUCTION. (PLATE MATERIAL: SA 516 GR 70, THKMM:15)	ROLLING OF INSERT PLATE AS PER ORIGINAL CONSTRUCTION. (PLATE MATERIAL: SA 516 GR 70, THKMM 14-16)

• In case of any query please contact at following

I/C Mechanical Section
OGDCL, Qadirpur Gas Field-Ghotki Sindh.
0723-660732
0723-660679
Planning qp@ogdcl.com
Mechanical_qp@ogdcl.com