

## Schedule of Requirement

## ANNEXURE-A

### Description and Quantity Requirements:

| S# | Description   | Unit Rate (Rs.) | Qty. Required | Total Rate (Inclusive all Taxes) (Rs.) | Remarks |
|----|---|-----------------|---------------|--|---------|
| 01 | <b>Explosion Proof Floodlight:</b><br>Ex mark: Ex db eb op is IIB T3 Gb Ex tb op is IIIC T150°C/T165°C Db<br>Intended use: Zone 1, zone 2, zone 21 and zone 22<br>Ambient temperature: -20°C to +40°C/+55°C<br>Degree of protection: IP66<br>Rated voltage: 220V AC 50 Hz<br>Power: High pressure sodium lamp 250W<br>Terminal: L1,N, cage type terminal 2x1.5-10mm <sup>2</sup> , PE terminal:2x2.5-6mm <sup>2</sup><br>Cable entry: Molded plastic 1xM25x1.5 cable gland, diameter: 8-17mm<br>Molded plastic 1xM25x1.5 stopping plug<br>Bracket mounting type |                 | 10 Nos        |  |         |
| 02 | <b>Non Explosion Proof Floodlight:</b><br>Flood light tango-3, type: MMF 383/250, complete with HPI-T 250W SON-T Lamp, ballast, capacitor & igniter. Clamp/bolt mounted   |                 | 30 Nos        |  |         |

### Terms and Conditions for Tender

1. Bids to be submitted on Single Envelope basis.
2. Evaluation criteria of the bids shall be "full consignment wise". (Technical & Financial evaluation shall be carried out on the complete scope of supply).
3. The parts to be delivered at Nashpa Oil Field. The delivery charges are in the scope of supplier/ bidder.
4. Any required technical clarification/details regarding the material to be supplied must be cleared before submission of bid. No change in submitted bid will be entertained after bid submission date.
5. The consignment will be accepted after final inspection at site, and payment will be made through Cross Cheque after inspection of material.
6. The firm should have valid NTN and GST number and have active status on FBR website.
7. The Firm should have active Professional tax certificate of concerned Excise office where operating business.
8. Tax submission Certificate (Annex-C) will be provided along with Invoice.
9. The spares to be supplied must be in original OEM packaging with standard warranty.