

OIL & GAS DEVELOPMENT COMPANY LIMITED
PROCUREMENT DEPARTMENT, ISLAMABAD
FOREIGN SECTION B

(To be completed, filled in, signed
and stamped by the principal)

ANNEXURE 'A'

Material 4-1/2 INCH CASING PIPES & CROSS OVERS
Tender Enquiry No PROC:FB/CB/D-4526/2019
Due Date
Evaluation Criteria FULL

SCHEDULE OF REQUIREMENT

Sr No	Description	Unit	Quantity	Unit Price (FOB)	Total Price (FOB)	Unit Price C & F BY SEA	Total Price C & F BY SEA	Deviated From Tender Spec. If Any
1	4-1/2" OD SEAMLESS STEEL CASING PIPES CONFORMING TO API SPECS 5CT, CAL-IV CONNECTION, R-3(Detail description attached)	Meter	2000					
2	4-1/2" CROSS OVERS AS PER DETAIL DESCRIPTION ATTACHED.	Number	2					

Note: NOTE:

01: PAYMENT WILL BE MADE AS PER THE FOREIGN PROCUREMENT PAYMENT TERMS AVAILABLE AT OGDCL WEBSITE (TENDERS TAB) EFFECTIVE FROM FEBRUARY 27, 2018.
02: PURSUANT TO TENDER CLAUSE # 2.2, 11.4, 13 & 35.3.2, A BID BOND OF USD 8,000/- OR EQUIVALENT IN PAK RUPEES, MUST BE SUBMITTED WITH THE TECHNICAL BID AND IT MUST BE VALID FOR 150 DAYS FROM THE DATE OF OPENING OF THE BID.

DETAIL DESCRIPTION OF 4-1/2" CASING & CROSS OVER (SOR)

1. 4-1/2" OD SEAMLESS STEEL CASING PIPE CONFORMING TO API SPECS 5CT, 10TH EDITION, WEIGHT 17 LBS/FT., BURST RATING > 18,000 PSI & COLLAPSE RATING > 19,000 PSI, MATERIAL GRADE SUITABLE FOR 3.68 % CO₂ & 5 PPM H₂S,(SUPER 13 CHROME OR SUPERIOR MATERIAL GRADE), CAL-IV PREMIUM THREAD CONNECTION, R-3 WITH STEEL/RUBBER THREAD PROTECTORS ON BOTH ENDS. PROPER COLOUR CODING ON COUPLING FOR GRADE IDENTIFICATION AND WITH OUTSIDE COATING FOR RUST PROTECTION DURING TRANSIT (DRIFT 3.615"). DELIVERY TOLERANCE -3 % IN QTY. QUANTITY = 2000 METERS
2. CROSS OVER SEAMLESS STEEL CASING PIPE CONFORMING TO API SPECS 5CT, 10TH EDITION, 4-1/2", 19.2 PPF, MATERIAL GRADE SAME AS QUOTED AGAINST SR # 1, VAM TOP PIN X HYDRIL PH-6 BOX CONNECTION, OVERALL LENGTH 4 FEET WITH STEEL/RUBBER THREAD PROTECTORS ON BOTH ENDS. PROPER COLOUR CODING ON COUPLING FOR GRADE IDENTIFICATION AND WITH OUTSIDE COATING FOR RUST PROTECTION DURING TRANSIT (DRIFT 3.515"). QUANTITY = 02 NOS

GENERAL TERMS & CONDITIONS

1. THE MANUFACTURERS/BIDDERS WILL BE REQUIRED TO QUOTE CFR KARACHI BY SEA PRICES FOR ALL THE ITEMS AS PER SOR.
2. EACH BIDDER/MANUFACTURER HAVE TO SUBMIT API 5CT PSL-3 (CASING GROUP 1 TO 4) LATEST VALID & BACK CERTIFICATES CONSECUTIVELY (NO BREAKS WILL BE ACCEPTABLE) FROM JANUARY 2009. (IN THIS REGARD PUBLISHED API COMPOSITE LIST OF YEAR JANUARY 2009 WILL BE CONSIDERED AS REFERENCE).
3. EACH BIDDER/MANUFACTURER HAVE TO SUBMIT VALID API-5CRA CERTIFICATE OF QUOTED PLANT/MILL. (SPECIFICATION FOR CORROSION-RESISTANT ALLOY SEAMLESS TUBES FOR USE AS CASING, TUBING, AND COUPLING STOCK, LATEST EDITION).
4. THE MANUFACTURER OF THE QUOTED MOTHER CASING PIPES & ITS THREADER SHOULD BE SAME (SINGLE MANUFACTURER).
5. THE CASING PIPE MANUFACTURING AND THREADING PLANT (ONE/SINGLE MANUFACTURER) MUST BE CERTIFIED BY API UNDER SPECS. 5CT-PSL-3 SINCE JANUARY 2009. PROCESSOR OF CASING PIPES WILL NOT BE CONSIDERED AS CASING PIPE MANUFACTURER.
6. DATA/SPECS SHEETS OF QUOTED CASING PIPES AS PER MANUFACTURER STANDARD TO BE PROVIDED BY THE BIDDER/MANUFACTURER.
7. THE TENSILE, BURST, COLLAPSE & COMPRESSION RATING OF THE QUOTED PREMIUM THREAD CONNECTION MUST BE EQUAL TO OR EXCEED THOSE OF THE PIPE BODY RATINGS. DOCUMENTS SUPPORTING THE REQUIREMENT SHOULD BE PROVIDED ALONG WITH THE BID.
8. THE PREMIUM CONNECTION QUOTED FOR 4-1/2" CASING/TUBING MUST BE CAL-IV CERTIFIED AS PER API RP 5C5:2017 (LATEST EDITION).
9. INCOMPLETE INFORMATION IN THE BID MAY LEAD TO NON-COMPLIANT & REJECTION OF BID.
10. DELIVERY ALLOWANCE OF +0 & -3% FOR CASING PIPES CAN BE ALLOWED, HOWEVER THE PAYMENT WILL BE MADE AS PER THE ACTUAL METERAGE OF CASING SUPPLIED. MORE THAN -3 % DELIVERY ALLOWANCE IS NOT ACCEPTABLE.
11. CASING PIPES SHOULD BE PROVIDED WITH MILLS PROTECTIVE COATING ON THE OUTSIDE.
12. THE CASING PIPES MUST BE BRAND NEW & UN-USED. CONFIRMATION TO THIS EFFECT IS REQUIRED IN THE TECHNICAL OFFER.
13. THE SUCCESSFUL BIDDER WILL BE REQUIRED TO FURNISH MILL INSPECTION CERTIFICATES FOR CASING PIPES WITH SHIPPING DOCUMENTS. CONFIRMATION TO THIS EFFECT MUST BE PROVIDED IN THE TECHNICAL OFFER.

14. LETTER IN ORIGINAL FROM THE MANUFACTURER(S) COVERING WARRANTY/GUARANTEE FOR A PERIOD OF 1-1/2 YEAR FOR THE QUOTED CASING PIPES TO BE SUBMITTED WITH THE TECHNICAL BID.
15. AUTHORITY LETTERS IN ORIGINAL FROM THE MANUFACTURER(S) TO BIDDER AND FROM BIDDER TO LOCAL AGENT FOR OFFERED CASING PIPES WITH TENDER ENQUIRY NUMBER MUST BE FURNISHED WITH THE TECHNICAL OFFER. THE AUTHORITY LETTER MUST BE ON COMPANY LETTER HEAD, SHOWING THE NAME AND CONTACT DETAILS (E-MAIL & FAX NUMBER) OF THE SIGNING AUTHORITY.
16. ORIGINAL BROCHURE OR BROCHURE ON CD/USB OF THE MANUFACTURER(S) CONTAINING TECHNICAL LITERATURE/SPECS SHEETS SPECIFYING PHYSICAL/PERFORMANCE PROPERTIES OF QUOTED CASING PIPES MUST BE SUBMITTED WITH THE TECHNICAL OFFER.
17. THE CASING PIPES MANUFACTURER MUST HAVE MANUFACTURED & SUPPLIED 4-1/2" SEAMLESS STEEL CASING/TUBING PIPES FROM YEAR 2009 TO THE MULTINATIONAL E&P COMPANIES LIKE EXXON, PDO, KOC, SHELL, BP, TOTAL, ENI, OMV, MOL, PPL AND OTHER INTERNATIONALLY RENOWNED E & P COMPANIES (NOT BELONGING TO THE MANUFACTURER'S OWN COUNTRY) IN EXCESS OF 10,000 METERS EACH YEAR. THE SUPPLY RECORD SHOULD INCLUDE ONLY THE SALES RECORD FOR 4-1/2" CASING/TUBING DURING EACH YEAR STARTING FROM YEAR 2009. IN THIS REGARD MANUFACTURER/BIDDER TO SUBMIT 10 UNPRICED COPIES OF DIFFERENT PURCHASE ORDERS SOLD TO 10 DIFFERENT E & P COMPANIES MENTIONED ABOVE. (DOCUMENTARY EVIDENCE TO PROVE THE EQUIVALENT STATURE OF E & P COMPANY OTHER THAN SPECIFIED ABOVE WILL BE REQUIRED ALONG WITH TECHNICAL BID, TO ASCERTAIN THE EQUIVALENCY OF E & P COMPANY OTHER THAN SPECIFIED ABOVE WILL BE OGDCL SOLE DISCRETION). CASING/TUBING PIPES SOLD TO SUPPLY/TRADING HOUSES & SERVICE COMPANIES ETC. WILL NOT BE CONSIDERED.
18. IF THE BIDDER/MANUFACTURER HAS NOT ALREADY SUPPLIED 4-1/2" CASING/TUBING PIPES TO OGDCL THEN 03 NOS CERTIFICATES OF SATISFACTORY PERFORMANCE FOR 4-1/2" CASING/TUBING PIPES ISSUED BY AUTHORIZED OFFICIALS OF AT LEAST 3 DIFFERENT MULTINATIONAL E&P COMPANIES LIKE EXXON, PDO, KOC, SHELL, BP, TOTAL, ENI, OMV, MOL, PPL AND OTHER INTERNATIONALLY RENOWNED E & P COMPANIES (NOT BELONGING TO THE MANUFACTURER'S OWN COUNTRY) MUST BE PROVIDED WITH THE TECHNICAL BID. THE CERTIFICATES MUST BE ON THE COMPANY LETTER HEAD AND SHOULD INDICATE THE NAME & DESIGNATION OF THE SIGNING AUTHORITY ALONG WITH HIS COMPLETE CONTACT DETAILS INCLUDING HIS OFFICIAL EMAIL ADDRESS IN ORDER TO VERIFY THE SAME. CERTIFICATES ISSUED BY SUPPLY/TRADING HOUSES & SERVICE COMPANIES ETC. WILL NOT BE CONSIDERED.
19. THIRD PARTY INSPECTION (TPI) BY INTERNATIONALLY REPUTED INSPECTION COMPANY IS REQUIRED AS PER OIL INDUSTRY PRACTICE. OGDCL WILL ARRANGE PRE- SHIPMENT INSPECTION OF THE CONSIGNMENT FROM ANY OF THE FOLLOWING THIRD PARTIES INSPECTION COMPANIES (I) M/S BUREAU VERITAS (II) M/S. SGS (III) M/S. TUV AUSTRIA (IV) M/S. VELOSI (V) M/S. TUV RHEINLAND. BIDDER/MANUFACTURER WILL PROVIDE FULL ASSISTANT TO INSPECTION COMPANY DURING INSPECTION. BIDDER TO CONFIRM THAT THIRD PARTY INSPECTION REPORT VERIFIED BY OGDCL WILL BE PROVIDED WITH THE SHIPPING DOCUMENTS FOR LC ENCASHMENT.

SCOPE OF WORK FOR TPI WILL BE AS FOLLOWS.
 - (I) FULL BODY ULTRASONIC INSPECTION.
 - (II) VISUAL THREAD INSPECTION.
 - (III) FULL BODY API DRIFT.
 - (IV) VERIFICATION OF MILL TEST CERTIFICATE.
20. EVALUATION CRITERIA IS FULL CONSIGNMENT WISE.
21. DELIVERY TIME REQUIRED IS 04 MONTHS C&F BY SEA KARACHI AFTER LC OPENING.