

OIL & GAS DEVELOPMENT COMPANY LIMITED
PROCUREMENT DEPARTMENT, ISLAMABAD
FOREIGN SECTION B

(To be completed, filled in, signed and stamped by the principal)

ANNEXURE 'A'

Material: PROCUREMENT OF CASING ACCESSORIES

Tender Enquiry No: PROC-FB/CB/DRLG/D-4957/2021

Due Date:

Evaluation Criteria: FULL

SCHEDULE OF REQUIREMENT

Sr No	Description	Unit	Quantity	Unit Price (FOB)	Total Price (FOB)	Unit Price C & F BY SEA	Total Price C & F BY SEA	Deviated From Tender Spec. If Any
1	14" FLOAT SHOE, P-110, 114 PPF, BTC BOX UP CONNECTION, DIFFERENTIAL FILL UP CIRCULATING DOUBLE FLAPPER VALVE, API RP 10 F CAT, IIB/IIC, IIB/IIC, PDC DRILLABLE (DRIFT 12.25" BIT).	Number	4					
2	14" FLOAT COLLAR, P-110, 114 PPF, BTC BOX UP X PIN DOWN CONNECTION, DIFFERENTIAL FILL UP CIRCULATING SINGLE FLAPPER VALVE, WITH NON-ROTATING PROFILE, API RP 10 F CAT IIB/IIC, IIB/IIC, PDC DRILLABLE (DRIFT 12.25" BIT).	Number	4					
3	9-5/8" FLOAT SHOE, MAT: Q125, HIGH COLLAPSE (MIN. COLLAPSE 11,000 PSI), 53.5 PPF, TSH BLUE BOX UP CONNECTION, DIFFERENTIAL FILL UP CIRCULATING DOUBLE FLAPPER VALVE, API RP 10 F CAT IIB/IIC, IIB/IIC, PDC DRILLABLE (DRIFT 8.5" BIT).	Number	5					
4	9-5/8" FLOAT COLLAR, MAT: Q125, HIGH COLLAPSE (MIN. COLLAPSE 11,000 PSI), 53.5 PPF, TSH BLUE BOX UP X PIN DOWN CONNECTION/DETAIL DESCRIPTION ATTACHED	Number	5					
5	NON-ROTATING TOP DISPLACEMENT CEMENTING PLUG, FIVE WIPER DESIGN (HNBR RUBBER), PLASTIC/POLYURETHENE INSERT CORE, PDC DRILLABLE, TO RUN IN 14" CASING RANGE 82.50 - 138.84 PPF & IN 13-3/8" CASING RANGE 48 -96 PPF.	Number	20					
6	NON-ROTATING BOTTOM DISPLACEMENT CEMENTING PLUG, FIVE WIPER DESIGN (HNBR RUBBER), PLASTIC/POLYURETHENE INSERT CORE, PDC DRILLABLE, TO RUN IN 14" CASING RANGE 82.50 - 138.84 PPF & IN 13-3/8" CASING RANGE 48 -96 PPF.	Number	15					
7	SHOE FLOAT, 9-7/8", TYPE: DOUBLE CIRCULATING FLAPPER VALVE, WEIGHT: 66.4# GRADE: 140KSI, CONNECTION: VAM 21, PDC DRILLABLE I/ASY CEMENT FLOAT SHOES.	Number	5					
8	COLLAR FLOAT, SIZE CASING: 9-7/8", TYPE: CIRCULATING FLAPPER VALVE, WEIGHT: 66.4# GRADE: 140KSI, CONNECTION: VAM 21, 1.75" DROP BALL, PDC DRILLABLE I/ASY CEMENT FLOAT COLLARS.	Number	5					
9	NON-ROTATING TOP DISPLACEMENT CEMENTING PLUG, FIVE WIPER DESIGN (HNBR RUBBER), PLASTIC/POLYURETHENE INSERT CORE, PDC DRILLABLE, TO RUN IN 9-7/8" & 9-5/8" CASING RANGE 32.30 - 70.30 PPF (DRIFT 8.5" BIT)	Number	20					
10	NON-ROTATING BOTTOM DISPLACEMENT CEMENTING PLUG, FIVE WIPER DESIGN (HNBR RUBBER), PLASTIC/POLYURETHENE INSERT CORE, PDC DRILLABLE, TO RUN IN 9-7/8" & 9-5/8" CASING RANGE 32.30 - 70.30 PPF (DRIFT 8.5" BIT).	Number	10					
11	CENTRALIZERS FOR 14" CASING, LATCH ON HINGED TYPE, NON-WELDED SPRING BOW TYPE, (14" CASING X 17" OPEN HOLE).	Number	100					
12	STOP COLLARS, FOR 14" CASING, LATCH ON HINGED TYPE WITH SPIRAL LOCKING PINS. (14" CASING X 17" OPEN HOLE).	Number	200					
13	CENTRALIZERS FOR 13-3/8" CASING, LATCH ON HINGED TYPE, NON-WELDED SPRING BOW TYPE. (MIN OD=14.685 MAX=18.388).	Number	500					
14	STOP COLLARS, FOR 13-3/8" CASING, LATCH ON HINGED TYPE WITH SPIRAL LOCKING PINS.	Number	1000					
15	CENTRALIZERS FOR 9-7/8" CASING, LATCH ON HINGED TYPE, NON-WELDED SPRING BOW TYPE. (MIN OD=11.142 MAX=14.843).	Number	30					
16	STOP COLLARS FOR 9-7/8" CASING, LATCH ON HINGED TYPE, WITH SPIRAL LOCKING PINS	Number	60					

OIL & GAS DEVELOPMENT COMPANY LIMITED
PROCUREMENT DEPARTMENT, ISLAMABAD
FOREIGN SECTION B

(To be completed, filled in, signed and stamped by the principal)

ANNEXURE 'A'

Material PROCUREMENT OF CASING ACCESSORIES

Tender Enquiry No PROC-FB/CB/DRLG/D-4957/2021

Due Date

Evaluation Criteria FULL

17	CENTRALIZERS FOR 9-5/8" CASING, LATCH ON HINGED TYPE, NON-WELDED SPRING BOW TYPE. (MIN OD=10.882MAX=14.583)	Number	1300
18	CENTRALIZERS FOR 7" CASING, LATCH ON HINGED TYPE, NON-WELDED SPRING BOW TYPE/NON-ROTATING TYPE. (MIN OD=8.232 MAX=10.616)	Number	800
19	STOP COLLARS FOR 7" CASING, LATCH ON HINGED TYPE, WITH SPIRAL LOCKING PINS	Number	1600
20	STOP COLLARS FOR 7" CASING, LATCH ON HINGED TYPE, FOR SPIRAGLIDER TYPE CENTRALIZERS	Number	100
21	CENTRALIZERS FOR 5" CASING, NON-WELDED, RIGID/ROTATING TYPE, MAX OD=5-3/4"	Number	100
22	STOP COLLARS FOR 5" CASING, NON-WELDED RIGID/ROTATING TYPE	Number	200
23	CASING STOP COLLAR 9-5/8" , FRICTION LOCK TYPE, HINGED, WITH BOLT ASSY.	Number	800

- Note:**
- BID BOND OF US \$ 6000/- OR EQUIVALENT PAK RUPEES MUST BE SUBMITTED WITH THE TECHNICAL BID WITH VALIDITY OF 150 DAYS BEYOND OPENING DATE.
 - BID VALIDITY IS 120 DAYS BEYOND OPENING DATE.
 - BIDDING PROCEDURE IS "SINGLE STAGE TWO ENVELOPE" MASTER SET OF TENDER DOCUMENT IS AVAILABLE ON OGDCL'S WEBSITE.
 - EVALUATION CRITERIA IS FULL CONSIGNMENT WISE.
 - DELIVERY PERIOD IS MENTIONED IN ATTACHMENT

Vetted as per approved insert.

09/02/21
 MUHAMMAD ISMAN AWAN
 SE (IMP)-III
 Ext: 2923

(Signature) 9/2/21

GENERAL TERMS & CONDITIONS

1. Valid/latest and 10 years back consecutive API 5CT certificates for the quoted single Manufacturer to be submitted with the technical Bid.
2. Technical Literature in original of offered casing accessories specifying comprehensive details should be submitted with the technical offer.
3. The manufacturer should have minimum ten (10) years' experience in the manufacturing of casing accessories (Float shoes, Float collars, Top & Bottom Cement Plugs, Centralizers & Stop Collars) and must have supplied the quoted casing accessories each year during last 10 years to the major international E & P & drilling contractor companies like Exxon, PDO, KOC, Shell, BP, Total, ENI, MOL, OMV, Schlumberger, Exalo etc or equivalent E & P and drilling contractor companies. In this regard bidder(s)/ manufacturer should provide last 10 (ten) years comprehensive detailed supply record other than manufacturer's own country containing detail of offered casing accessories, quantity sold & name of customers. Moreover unpriced copies of at least 10 different (different E & P/drilling contractor companies) purchase orders for quoted casing accessories other than manufacturer's own country should also be submitted with technical bid. The supply record must be on the company letterhead and should indicate the Name & Designation of the signing authority along with his complete contact details phone & fax numbers and his official email address. (Documentary evidence to prove the equivalent stature of E & P Company/ Drilling contractors other than specified above will be required along with technical bid, to ascertain the equivalency of E & P Company/ Drilling contractors other than specified above will be OGDCL sole discretion).
4. If manufacturer has not already supplied quoted casing accessories to OGDCL then certificates of satisfactory performance of quoted casing accessories issued by authorized official(s) of at least 3 (Three) different renowned international E&P companies like Exxon, PDO, KOC, Shell, BP, Total, ENI, MOL, OMV or equivalent E & P company and drilling contractor companies like Schlumberger, Exalo or equivalent drilling contractor company other than manufacturer's own country in favour of quoted manufacturer should be submitted with the technical offer. If manufacturer has already supplied quoted casing accessories to OGDCL then its performance will be evaluated on in house report. The certificates must be on the company letterhead and should indicate the Name & Designation of the signing authority along with his complete contact details phone & fax numbers and his official email address. However above certificate(s) issued by joint ventures and supply/trading house(s) will not be accepted. (Documentary evidence to prove the equivalent stature of E & P Company/ Drilling contractors other than specified above will be required along with technical bid, to ascertain the equivalency of E & P Company/ Drilling contractors other than specified above will be OGDCL sole discretion).
5. The successful bidder will be required to furnish mill inspection certificate for quoted casing accessories with final shipping documents. Confirmation to this effect should be provided in the technical offer.
6. Original letter from the manufacturer(s) covering Warranty/Guarantee for offered casing accessories for a period of 18 months from date of shipment with tender enquiry number must be furnished with the technical offer.
7. Authority letters in original from the manufacturer(s) to bidder and from bidder to local agent for offered casing accessories with tender enquiry number must be furnished with the technical offer. The authority letter must be on company letter head, showing the name and contact details (E-mail & fax number) of the signing authority.



8. The offered casing accessories should be brand new & un-used. Confirmation to this effect is required in the technical offer.
9. All offered float shoes and float collars should be PDC drillable.
10. Third party inspection will be carried out as per oil industry practice. TPI will be arranged by OGDCL from any of the following parties (i) M/S SGS Pakistan (Private) Limited, Pakistan (ii) M/S Bureau VERITAS Pakistan (Pvt) Ltd, Pakistan (iii) M/S TUV Austria Bureau of inspection & certification (Pvt) Ltd, Pakistan (iv) M/s TUV Rheinland Arabia LLC, Pakistan (v) M/S Velosi, Pakistan. Bidder will assist and make necessary arrangement for TPI. Bidder to confirm that TPI report verified by OGDCL will be provided with shipping documents for encashment of LC.

SCOPE OF WORK FOR TPI

Third party inspection agency will carry out the required inspection according to the scope of work including but not limited to the following terms of reference (T.O.R).

- (i). Verification that all materials are brand new and unused.
 - (ii). Verification that all the materials (quantity & specifications) & documents are in accordance with Purchase order.
 - (iii). Verification/ Confirmation of API Drift (as per Purchase order) for float shoes, float collars & where applicable.
 - (iv). Visual body & thread inspection of all float shoes & float collars & where applicable for any defects.
 - (v). Verification of mill inspection certificates & certificate of conformance.
 - (vi). Full process inspection from the start of manufacturing as per industry traceability level five (5) which includes performance & test reports, trace matrix and material certificates.
11. Evaluation will be full consignment wise basis.
 12. Delivery required within two (02) months after establishment of Letter of Credit CFR Karachi by sea.

