

**OIL & GAS DEVELOPMENT COMPANY LIMITED**  
**PROCUREMENT DEPARTMENT, ISLAMABAD**  
**FOREIGN SECTION B**

(To be completed, filled in, signed and stamped by the principal)

ANNEXURE 'A'

Material Procurement of 7" & 5" Casing for Wali Wells

Tender Enquiry No PROC-FB/CB/DRLG/D-5395-A/2022 *(M)*

Due Date

Evaluation Criteria GROUP WISE

**SCHEDULE OF REQUIREMENT**

Sr No	Description	Unit	Quantity	Unit Price (FOB)	Total Price (FOB)	Unit Price C & F BY SEA	Total Price C & F BY SEA	Deviated From Tender Spec. If Any
-------	-------------	------	----------	------------------	-------------------	-------------------------	--------------------------	-----------------------------------

**Group A**

1	7" OD, seamless steel casing pipes conforming to API specs 5CT, 10th edition, Grade L-80, 13 Chrome, Weight 35 lbs/ft, PSL-3, Vam21/TSH Blue or equivalent CAL-IV connection, R-3 (Drift 5 7/8" bit), DETAIL DESCRIPTION ATTACHED.	Meter	2000					
---	--	-------	------	--	--	--	--	--

**Group B**

2	5" OD, seamless steel casing pipes conforming to API specs 5CT, 10th edition, Grade Min 95 Ksi, 13 Chrome, Weight 18 lbs/ft, PSL-3, VAM SLIJ-II or equivalent semi flush connection, R-3 (Drift 4 1/8" bit), DETAIL DESCRIPTION ATTACHED.	Meter	2300					
3	Lifting Sub for 5" OD casing, 95 Ksi, Weight 18 lbs/ft, VAM SLIJ-II or equivalent semi flush connection	Number	4					

**Note:** I. BID BOND FOR GROUP A IS US \$ 17,450/- & GROUP B IS US \$ 11,550/- EQUIVALENT PAK RUPEES MUST BE SUBMITTED WITH THE TECHNICAL BID WITH VALIDITY OF 150 DAYS BEYOND OPENING DATE.  
 ii. BID VALIDITY IS ~~60~~ <sup>45</sup> DAYS BEYOND OPENING DATE.  
 iii. BIDDING PROCEDURE IS "SINGLE STAGE SINGLE ENVELOPE" MASTER SET OF TENDER DOCUMENT IS AVAILIABLE ON OGDCL'S WEBSITE.  
 iv. EVALUATION CRITERIA IS EACH GROUP WISE.  
 v. DELIVERY PERIOD IS MENTIONED IN TOR'S

*vetted  
 Yaswan  
 18/08/22*

## DETAIL DESCRIPTION, SCHEDULE OF REQUIREMENT (SOR)

### GROUP-A

1. 7" OD, SEAMLESS STEEL CASING PIPE CONFORMING TO API SPECS 5CT, 10TH EDITION, GRADE L-80, 13 CHROME, WEIGHT 35 LBS/FT, VAM21/TSH BLUE OR EQUIVALENT CAL-IV THREAD CONNECTION, PSL-3, R-3 COUPLED WITH SURFACE TREATMENT WITH COPPERPLATING AND WITH PLASTIC TYPE CLOSED END THREAD PROTECTORS ON BOTH ENDS. PROPER COLOUR CODING ON COUPLING FOR GRADE IDENTIFICATION AND WITH OUTSIDE COATING FOR RUST PROTECTION DURING TRANSIT (DRIFT 5-7/8" BIT). DELIVERY TOLERANCE -3 % IN QTY.2000M QUANTITY METERS

### GROUP-B

2. 5" OD, SEAMLESS STEEL CASING PIPES CONFORMING TO API SPECS 5CT,10TH EDITION, GRADE MIN 95 KSI, 13 CHROME, WEIGHT 18 LBS/FT, VAM SLIJ-II OR EQUIVALENT SEMI FLUSH CONNECTION, PSL-3, R-3 (DRIFT 4 1/8" BIT), DELIVERY TOLERANCE -3 % IN QTY.2300M QUANTITY METERS

3. LIFTING SUB FOR 5" OD CASING, 95 KSI, WEIGHT 18 LBS/FT, VAM SLIJ-II OR EQUIVALENT SEMI FLUSH CONNECTION, QUANTITY=04NOS

### GENERAL TERMS & CONDITIONS

1. The Manufacturers/Bidders will be required to quote CFR Karachi by Sea Prices for all the items as per SOR.
2. Bidders quoting against Group-A & Group-B Casing have to submit quoted Manufacturer plant/plants API 5CT PSL-3 latest valid & back certificates consecutively (no breaks will be acceptable) from January 2010. (In this regard published API composite List of January 2010 will be considered as Reference).
3. The Manufacturer of the quoted mother casing pipes & its threaded should be same (Single Manufacturer).
4. The Casing Pipe manufacturing and threading plant (One/Single Manufacturer) must be certified by API under Specs. 5CT-PSL-3 since January 2010. Processor of Casing Pipes will not be considered as casing pipe Manufacturer.
5. Data/Specs sheets of quoted Casing Pipes as per Manufacturer standard to be provided by the Bidder/Manufacturer.
6. The Tensile, Burst, Collapse & compression rating of the Quoted Premium Thread Connection must be equal to or exceed those of the Pipe body ratings. Documents supporting the requirement should be provided along with the bid.

*vetted  
yaman  
31/08/2022*

7. All offered Thread & Coupled Premium connections must be CAL-IV Certified for offered Casing pipes. Manufacturer must provide copy of a report showing the compatibility of the connection family testing/qualification records with extrapolation/interpolations rules as per Section "G" of ISO 13679:2002/API 5C5 (Recommended Practice for testing casing & tubing connection) with the technical offer. Otherwise, a test report of the quoted premium threads casing for the exact OD, PPF & yield strength showing complete ISO-13679:2002/API 5C5's Application Level CAL-IV test (8 specimens with make & break + baking + Series A, B, C + Failure Tests). Any deviation in this regard is not acceptable. Documentary evidence to this effect must be submitted with the Technical offer (for Group-A only).
8. Delivery allowance of +0 & -3% for Casing Pipes can be allowed, however the payment will be made as per the actual Meterage of Casing supplied. More than -3 % delivery allowance is not acceptable. Applicable to Casing Group-A & Group-B of SOR.
9. Casing Pipes should be provided with mills protective coating on the outside. Applicable to Casing Group-A & Group-B of SOR.
10. The casing pipes must be brand new & un-used. Confirmation to this effect is required in the technical offer.
11. The successful bidder will be required to furnish mill inspection certificates for casing pipes with shipping documents. Confirmation to this effect must be provided in the technical offer.
12. Letter in original from the manufacturer(s) covering Warranty/Guarantee for a period of 1-1/2 year from date of shipment for the quoted casing pipes & casing accessories to be submitted with the technical Bid.
13. Authority letters in original from the manufacturer(s) to bidder and from bidder to local agent for offered casing pipes with tender enquiry number to be furnished with the technical offer. The authority letter must be on company letter head, showing the name and contact details (E-mail & fax number) of the signing authority.
14. Original Brochure or broche on CD/USB of the manufacturer(s) containing technical literature/specs sheets specifying physical/performance properties of quoted casing pipes & casing accessories to be submitted with the technical offer.
15. The Casing pipes manufacturer must have manufactured & supplied seamless steel Casing pipes to the multinational companies like Exxon, PDO, KOC, SHELL, BP, TOTAL, ENI, OMV, MOL, PPL and other Internationally renowned E & P companies (not belonging to the manufacturer's own country) in excess of 20,000 Meters each year during the last Ten (10) years for items at Group A & B. The supply record must confirm this fact. The supply record should include only the sales record for offered casing pipes during each year. Applicable to Casing Group-A & Group-B of SOR.
16. If the Manufacturer has not already supplied the quoted casing pipes & casing against Group-A & Group-B of SOR to OGDCL then Manufacturer/Bidder to submit 10 unpriced copies of different Purchase orders against each quoted item sold to 10 different E & P companies mentioned above (not belonging to the manufacturer's own country). (Documentary evidence to prove the equivalent stature of E & P company other than specified above will be required along with technical bid, to ascertain the equivalency of E & P company other than specified above will be OGDCL sole discretion). Casing Pipes sold to supply/Trading houses & services companies etc.
17. If the bidder/Manufacturer has not already supplied offered Casing Pipes against each quoted item of Group-A & Group-B to OGDCL then 05 Nos certificates of satisfactory performance for each quoted casing pipes & casing accessories issued by authorized officials of at least 5 different multinational E&P companies like Exxon, PDC, KOC, SHELL, BP, TOTAL, ENI, OMV, MOL, PPL and other Internationally renowned E & P companies (not belonging to the manufacturer's own



country) must be provided with the technical bid. The certificates must be on the company letter head and should indicate the Name & Designation of the signing authority along with his complete contact details including his official email address in order to verify the same. (Documentary evidence to prove the equivalent stature of E & P Company other than specified above will be required along with technical bid, to ascertain the equivalency of E & P Company other than specified above will be OGDCL sole discretion). Certificates issued by supply/Trading houses & service companies etc. will not be considered.

18. Third party inspection (TPI) by internationally reputed inspection company is required as per oil industry practice. OGDCL will arrange inspection during manufacturing and before shipment of the consignment from any of the following third parties inspection companies (i) M/S Bureau Veritas (ii) M/S. SGS (iii) M/S. TUV Austria (iv) M/S. Velosi (v) M/S. TUV Rheinland. Bidder/manufacturer will provide full assistant to Inspection Company during inspection. Bidder to confirm that third party inspection report verified by OGDCL will be provided with the shipping documents for LC encashment.

Scope of work for TPI will be as follows but will not be limited to this.

(i) Full body ultrasonic inspection where applicable.

(ii) Visual thread inspection.

(iii) Full body API drift.

(iv) Verification of mill test certificate.

(v) Pre-shipment inspection to confirm that shipment is as per Issued PO w.r.t quantity, Packing, Specifications, brand new & unused, weight, length, thread protectors, coating etc

19. Evaluation criteria is each Group Wise.

20. Delivery time required is 07 Months C&F by sea Karachi after LC opening.

~~✗~~