

OIL & GAS DEVELOPMENT COMPANY LIMITED
PROCUREMENT DEPARTMENT ISLAMABAD
FOREIGN SECTION A

(To be completed, filled in, signed and stamped by the principal)

ANNEXURE 'A'


Material DEMISTER PADS FOR VARIOUS PRESSURE VESSELS AT DAKHNI PLANT
Tender Enquiry No PROC-FA/CB/P&P/DKN-4546/2019
Due Date
Evaluation Criteria FULL

01/05

SCHEDULE OF REQUIREMENT

Sr No	Description	Unit	Quantity	Unit Price (FOB)	Total Price (FOB)	Unit Price C & F BY SEA	Total Price C & F BY SEA	Deviated From Tender Spec. If Any
1	PAD, DEMISTER + COALESCER LAYER, W/GRIDS, DIA 948MM, THK 583MM, SS 316, LOWER PAD: 3 PCS, UPPER PAD: 4 PCS. As Per TOR & Drawings Attached	Number	6					
2	PAD, DEMISTER WITH GRIDS, IN 1 PC, DIA 435MM, THK 150MM, SS 316. As Per TOR & Drawings Attached	Number	3					
3	PAD, DEMISTER WITH GRIDS, IN 2 PCS, DIA 758MM, THK 153MM, SS 316. As Per TOR & Drawings Attached	Number	2					
4	PAD, DEMISTER WITH GRIDS, IN 3 PCS, DIA 945MM, THK 153MM, SS 316. As Per TOR & Drawings Attached	Number	6					

- Note:**
- 1) PURSUANT TO TENDER CLAUSE # 2.2, 11.4, 13 & 35.3.2, BID BOND AMOUNTING TO USD 500/- OR EQUIVALENT TO PAK RUPEES MUST BE SUBMITTED WITH THE TECHNICAL BID AND VALID FOR 150 DAYS FROM THE DATE OF OPENING OF THE BID.
 - 2) EVALUATION CRITERIA: FULL CONSIGNMENT WISE ON CFR KARACHI BASIS.
 - 3) TERMS AND CONDITIONS: BIDDERS ARE ADVISED TO CAREFULLY READ ALL THE TERMS AND CONDITIONS OF THE TENDER DOCUMENT AVAILABLE AT OGDCL WEBSITE IN THE MASTER SET OF TENDER DOCUMENT.
 - 4) SHIPMENT FROM ASIAN CLEARING UNION (ACU) MEMBER COUNTRIES: IN CASE OF SHIPMENT FROM ACU MEMBER COUNTRIES, THE LC BENEFICIARY SHOULD BE OF THAT PARTICULAR COUNTRY FROM WHERE THE CONSIGNMENT IS BEING SHIPPED.
 - 5) SUMMARY REJECTION CRITERIA: THE SUMMARY REJECTION CRITERIA CLAUSE # 35 OF OGDCL MASTER SET OF TENDER DOCUMENT MAY ALSO BE EXAMINED CAREFULLY. ANY BID NOT MEETING THE CRITERIA SPELLED IN THE CLAUSE # 35 SHALL BE SUMMARILY REJECTED WITHOUT ANY RIGHT OF APPEAL.
 - 6) DELIVERY PERIOD: THE DELIVER PERIOD OF THE QUOTED MATERIAL SHOULD NOT BE MORE THAN 90 DAYS AFTER OPENING OF LETTER OF CREDIT (LC).
 - 7) **PAYEMNT:**
 - a) **FOR TENDER VALUE LESS THAN OR EQUAL TO US\$ 200,000:**
 PAYMENT TO THE CONTRACTOR/ BIDDER IN FOREIGN CURRENCY SHALL BE MADE BY ESTABLISHING IN FAVOR OF THE CONTRACTOR AN IRREVOCABLE LETTER OF CREDIT (HEREINAFTER CALLED THE L/C). 70 % PAYMENT (S) UNDER THE L/C WILL BE MADE FOR THE FOB/ CFR / CPT (AS THE CASE MAY BE) PRICE OF MATERIAL OF EACH SHIPMENT UPON SUBMISSION OF THE SHIPPING DOCUMENTS. BALANCE 30% PAYMENT WILL BE RELEASED AFTER RECEIPT, INSPECTION AND ACCEPTANCE OF MATERIAL.
 - b) **FOR TENDER VALUE MORE THAN US\$ 200,000:**
 PAYMENT TO THE CONTRACTOR/ BIDDER IN FOREIGN CURRENCY SHALL BE MADE BY ESTABLISHING IN FAVOR OF THE CONTRACTOR AN IRREVOCABLE LETTER OF CREDIT (HEREINAFTER CALLED THE L/C). 80 % PAYMENT (S) UNDER THE L/C WILL BE MADE FOR THE FOB/ CFR / CPT (AS THE CASE MAY BE) PRICE OF MATERIAL OF EACH SHIPMENT UPON SUBMISSION OF THE SHIPPING DOCUMENTS. BALANCE 20% PAYMENT WILL BE RELEASED AFTER RECEIPT, INSPECTION (IN ADDITION OF PRE-SHIPMENT INSPECTION) AND ACCEPTANCE OF MATERIAL.


checked

 17/05/19
 H. SIDDIQI (General Manager)
 In-charge (Branch) P&P-NE
 Ext: 2624

02/05

TENDER ENQUIRY # PROC-FA/CB/P&/DKN-4546/2019**TOR for Demister Pads for Pressure Vessels installed at Dakhni Plant**

Sr. #	Description	Required Quantity in Nos.	Drawing No
1.	Demister Pad + Coalescer Layer, With Grids DIA 948MM, THK 583MM, SS 316 LOWER PAD: 03 Pieces UPPER PAD: 04 Pieces	6	NS7/3/148 REV.3
2.	Demister Pad With Grids, DIA 435MM, THK 150MM, SS 316 IN 01 Piece	3	N/A
3.	Demister Pad With Grids, DIA 758MM, THK 153MM, SS 316. IN 02 Pieces	2	N/A
4.	Demister Pad With Grids DIA 945MM, THK 153MM, SS 316. IN 03 Pieces	6	SK4/5468/REV 03

- Bidder should strictly adhere to the specifications mentioned in the Schedule of requirement and drawings.
- Compliance of the material with NACE-MR-0175 (sour gas service).
- The manufacturer must have 10 years of experience of manufacturing of the demister pads. Documentary evidence to this effect along with Profile of company must be submitted with technical bid.
- Bidder should submit the authorization letter from the manufacturer to participate in the tender enquiry.**
- Delivery period must not exceed **90 days** from LC opening.
- Bid should be submitted on C&F by Sea Karachi basis.
- In case, if bidder is not manufacturer, then bidder to confirm the company profiles, experience of supplies (Previous Purchase Orders) in oil & Gas Sector along with technical bids.
- Bid will be valid for **120 days** from the date of bid opening.
- Manufacturer must be ISO 9001 Certified. Valid Certificate should be provided with the bid.
- Complete compliance certificate should be provided with the technical bid.


 N. ANSARI
 In. Engr. (Mech.) P&P-NB
 Ext: 2084



03/05

Begg, Cousland & Co. Ltd.

ENQ. N° 1833

SK4/5468 Rev 1

Date: 13/3/86



PLAN

DEMISTER:- 316S/S — TYPE 'H' — 3 OFF (EACH IN 3 SECTNS)

GRIDS:- (6mm DIA) — 316S/S — 6 OFF (EACH IN 3 SECTNS)

JOB N° 52/2437/86 ITEM 2/3

Customer:- B.S. & B.
(NETHERLANDS)

DIAL HT. WAS 150mm A/B

ORG NO NST/3/148

PREVIOUS EDR NOS

RE

UPPER PAD

25x3
FLAT BAR

SECT'S DESIGNED TO
PASS A 41 1/2 M/HR
(FOR SUPPORT OUTLINE SEE SK4/5401 REV3)

LOWER PAD



5x3 FLAT BAR

LOW DIA.
SPACER RODS.


SUPPORT SCREENS
CENTRE

583 ±0
O/A.

(WHEN ASSEMBLED)
FLOW DIRECT




948 DIA. PAD.
(11 ADDED FOR COMP) 316



6 DIA. CROSS RODS @ 150 CTRS
(TYPICAL)

6 DIA CROSS RODS @ 150 CTRS
(TYPICAL)

CLUST:-
B.S & B NETHERLANDS



DETAIL 1
(GRID ONLY)

'A' = 75mm THK. TYPE 'H'
DEMISTER - 316 S/S
'B' = 75mm THK. TYPE 'H'
COALESCER - 316 S/S + GLASS FIBRE.

JOB N° 52/2437/B6 ITEM 1/3

ADDITIONAL NOTES	PARTS DESCRIPTION & MATERIALS		TITLE:-
SPACER RODS:- 316 S/S 6mm DIA.	DEMISTER/COALESCER UNIT:- 3 OFF	3 FLOW DIRECT ADDED (28/4/86)	DEMISTER/COALESCER
60 OFF AT 327mm LONG	SUPPORT GRIDS:- 316 S/S - 3 UPPER 3 LOWER	2 UPPER PAD WAS 12.5 FEET (17/4/86)	DRN BY [Signature] DATE 5/11/85
42 OFF AT 252mm LONG	SUPPORT SCREENS:- 2" X 1/2" 316 S/S - 3 UPPER 4" X 1/2" 316 S/S - 3 LOWER	1 PAD DIA. WAS 948 P.F.S. 930 P VESSEL (13/7/86)	CHKD BY [Signature] DATE
	4" X 1/2" LONG BOUNDARY WIRE. 3 LOWER	REVISIONS	DRG NO NST/3/148 REV. 3




BEGG COUSLAND & CO. LTD.
SPRINGFIELD WIRE WORKS
636 SPRINGFIELD ROAD
GLASGOW



04/05

[Handwritten signature]


05/05



ITEM 2
Demister with grids,
in 3 pieces
Dia: 945mm
Thickness: 153mm
Material: SS316



ITEM 3
Demister with grids,
in 2 pieces
Dia: 758mm
Thickness: 153mm
Material: SS 316



OK