

**OIL & GAS DEVELOPMENT COMPANY LIMITED
PROCUREMENT DEPARTMENT ISLAMABAD
FOREIGN SECTION**

(To be completed, filled in, signed
and stamped by the principal)

ANNEXURE 'A'

Material HAULAGE TRUCKS
Tender Enquiry No PROC-FE/CB/ECMP-4842A/2021
Due Date
Evaluation Criteria MAIN ITEM

SCHEDULE OF REQUIREMENT

Sr No	Description	Unit	Quantity	Unit Price (FOB)	Total Price (FOB)	Unit Price C & F BY SEA	Total Price C & F BY SEA	Deviated From Tender Spec. If Any
1	BRAND NEW 4X4(RIGHT HAND DRIVE)HAULAGE TRUCK (specification terms & conditions # EW-17/001-A/2021 attached)	Number	20					

Note:

NOTE:

1. **Bid Validity:** Bid must be **valid for 180 days** from the date of Technical Bid Opening
2. **Bid Bond Amount:** USD 36,000/- (United States Dollar Thirty Six Thousand only) or equivalent Pak Rupees **valid for 210 days** from the date of Technical Bid Opening. Bidders are advised to carefully read all clauses related to Bid Bond in "Master Set of Tender Document-Single Stage Two Envelope-Foreign" available on OGDCL website
3. **Evaluation Criteria:** - Main Equipment Wise CFR Karachi
4. **Delivery Period:** 06 months from establishment of LC
5. Bidders are advised to carefully read all the terms and conditions of the Tender Document "Master Set of Tender Document-Single Stage Two Envelope-Foreign" available on OGDCL website which is an integral part of this Schedule of Requirement

Oracle Attachment

TECHNICAL SPECIFICATION OF BRAND NEW 4X4 HAULAGE TRUCKS
 Requisition No.: - EW-17/001-A/2021 Dated: - 29-03-2021

Sr. No	DESCRIPTIPON	P.NO
1.	<u>BRAND NEW LATEST MODEL (RIGHT HAND DRIVE)4X4 HAULAGE TRUCKS (CARGO CUM CREW CARRIER TRUCK).</u>	
2	<p><u>Engine Specifications</u></p> <p>Six cylinder, 4-stroke in line,6 cylinder direct fuel Injection type turbocharged water cooled diesel engine at least EURO-III, Net flywheel horse power (HP)220 to 260 at 2200 to 2900 RPM with the following specification and accessories: -</p> <p>I. Clutch: - Dry single Plate with Hydraulic Booster control</p> <p>II. Transmission: - Six Forward, one Reverse speed with low & high gear option.</p> <p>III. GVW Rating: - 13000 KG to 16000 KG</p> <p>IV. Overall vehicle length: - 6400 to 6800 mm</p> <p>V. Overall Vehicle Width: - 2450 to 2600 mm</p> <p>VI. Overall Vehicle Height: - 2750 to 3000 mm</p> <p>VII. Wheel Base: - 3600 to 4000 mm</p> <p>VIII. Ground clearance: - 275 to 350 mm</p> <p>IX. Steering: - Power steering (with Hydraulic Booster)</p> <p>X. Tyre size: - 13.00. R20 or 14.00. R20 (20-22 PR) (All terrain/Weather) Single Radial tyre at front and rear.</p> <p>XI. Breaks: - Air/Hydraulic (Brake with dual circuit).</p> <p>XII. Suspension: - Front & Rear Parabolic with shock absorber.</p> <p>XIII. Axle: - Full floating, double reduction front and rear.</p>	

BM

XIV. Cabin: -

Tilting type equipped with standard accessories.

XV. Instrument Panel: -

Speedometer, with trip meter, RPM meter, Oil gauge, fuel gauge, water temperature & air pressure gauges etc.

3

ACCESSORIES

I. Spare Wheel with holder fitted at suitable place.

II. Rear towing hook (3500 Kg), Front sockless hook.

III. Standard tool kit for each.

IV. First aid box with each Truck.

V. Fire extinguisher to be provided inside the driver cabin.

VI. Brake coupling for towing of trailer.

VII. Electrical socket for towing of trailer.

VIII. Safety Belts for cabin crew

IX. Front protection guard for Radiator & Lights.

4

CONSTRUCTION OF TRUCK BODY

I. Floor: - Checquet steel sheet

II. Side Panels: - Pressed steel section

III. Front Board: - Pressed steel section

IV. Canopy: - MS Pipe

V. Body Mounting: - U-Bolt/Fish Plate/Pin bolt

VI. Canopy cover: - Water proof Canvas.

VII. SEATS: - Bench type folding seats with seat belt, fitted with wooden planks.

5

PAINT OF TRUCK

I. Primer All parts coated with oven baked epoxy primer

II. Paint 2K Paint Green/Sand Beige.

6

SPARE PARTS FOR TRUCKS.

Bidder must provide one year running unpriced parts list including engine top overhauling parts with the technical

bid and priced list of parts to be provided with the financial bid. The cost of spares should not exceed 10% of the total cost of main equipment. The cost of spare will not be included in financial evaluation.

7 WORK SHOP MANUALS AND DIAGNOSTIC TOOL

- I.** Workshop repair, operation/maintenance manual and parts catalogue in *English*. (Hard & Soft copy) **(06 Sets)**.
- II.** Diagnostic Tool with valid life time license, if required **(02 Sets)**.


8 INSPECTION AND START-UP.

- I.** Third party pre-shipment inspection of the vehicles shall be carried out as per OGDCL procedure on the manufacturer premises. Scope of work for TPI will be shared with manufacturer at suitable time. The manufacturer will provide full support to third party inspector during the inspection & testing process.
- II.** Third party inspection will be monitored by 02 officials from the indenting department at OGDCL cost.
- III.** Final inspection shall carry out after arrival of consignment in Pakistan.
- IV.** Start-up/ commissioning of equipment in Pakistan will be the responsibility of the bidder *through its authorized representative for ten working days*. (Air ticket, boarding, lodging, transport and security of representative will be the responsibility of the bidder/local agent)
- V.** Bidder will quote and confirm to provide standard training regarding operation, repair & maintenance of trucks, for 02 Nos. OGDCL professionals, for two (weeks), at bidder's training facility at OGDCL cost. However, training cost will not be part of financial evaluation and separate case will be initiated by indenting department in this regard.

9 WARRANTY.

The bidder must provide the warranty of complete package for minimum 50000 K/M. or two years which come first, warranty will be started after commissioning of equipment in Pakistan.

10 TERMS & CONDITIONS

- I.** Original equipment manufacturer (OEM) or its authorized dealer can participate in bidding process. In case the bidder is authorized dealer then bidder must provide the dealership certificate on OEM letter head, along with technical bid.
 - II.** Original equipment manufacturer must have minimum 20 years' experience in manufacturing of the said type of (4X4) Vehicles. The bidder must submit documentary evidence i.e. OEM letter head in this connection.
- 

- III.** OEM must provide last (10 years) sale record with technical bid showing sale of at least 150 No's of quoted or similar 4X4 Vehicles on original letter head with address, Phone / Fax No & e-mail address of buyer for confirmation.
- IV.** OEM will provide certificate of performance from different 03 well renowned companies other than country of origin. The certificate must be on buyer company letter head and should indicate name and designation of signing authority along with complete phone, fax and e-mail address for verification.
- V.** Bidder must provide original Brochures, detailed technical specifications in English of quoted model with technical bid.
- VI.** OEM must provide an undertaking for the availability of **spares parts** and after sales service in Pakistan for at least 10 years' itself or through authorized dealer / workshop with address, telephone No. & e-mail address in Pakistan along with the bid for confirmation.
- VII.** Third party pre-shipment inspection of equipment will be arranged by OGDCL at manufacturer's facility before shipment. **Without 3rd party pre-shipment inspection the equipment will not be shipped nor accepted.**
- VIII.** All the bidders are advised to comply with tender specifications without any deviation and submit the complete bid in original. **Scanned / Faxed copy and incomplete bid will not be accepted for technical evaluation.**
- IX.** Delivery period **6 Months.**
- X.** Copy of valid ISO 9001/API/EC certificate or equal international quality standard Certification must be provided with technical bid.

Note: - Para wise original compliance sheet from 1 to 10 dully signed & stamped by the bidder with offered model/main specification/size etc. should Clearly be provided with technical bid for technical evaluation/inspection.