



**OIL AND GAS DEVELOPMENT COMPANY LIMITED**  
**BETTANI OIL & GAS FIELD**

TENDER NO. TE/BOGF/Elect-07/2024

DATE: 08/10/2024

**Schedule Of Requirement / TOR :**

S/No	Description	A/U	Qty
1	<p><b><u>Main Distribution Panel:</u></b></p> <p>Panel Board: 14 SWG, Panel Size: 1500 x1000(500x500) x 500mm (xyz) Having Outdoor Canopy and proper Floor Mounting</p> <p><b><u>Incoming:</u></b></p> <p>MCCB: 600A Indication Light R/Y/B (09 No) Control Fuse 2A with Base</p> <p><b><u>Outgoing:</u></b></p> <p>MCCB 250A: 3No MCCB 100A: 3No, (100A, RCCB Fitted with Each MCCB) MCB 63A: 5No, (60A, RCCB Fitted with Each MCCB) MCB 32A: 6No, ((40A, RCCB Fitted with Each MCCB)) MCB 20A: 3No (25A, RCCB Fitted with Each MCCB) MCB 16A: 3No Bus Bar and Insulator: as per rated specifications</p>	No	1
2	<p><b><u>Explosion Proof Distribution Panel:</u></b></p> <p>Incoming: MCCB 250A Out Going: MCB 63A (3No), (60A, RCCB Fitted with Each MCCB) Fitted With Photocell for Automatic Lighting On/Of Bus Bar, Insulator and indication lights: as per rated specifications</p>	No	3
3	<p><b><u>Lighting Distribution Panels</u></b></p> <p>Size: 2'x2'x1'</p> <p>Incoming: 100A Outgoing: 50A with Magnetic Contactor and Photo cell 50A without magnetic Contactor</p>	No	5

<b>4</b>	<p><b><u>Outdoor Distribution Panel</u></b></p> <p>Size: 800x600x200MM</p> <p>Incoming 250A</p> <p>Outgoing: 100A = 03No Each fitted with 100A RCCB</p> <p>63A = 03 NO Each Fitted with 60A RCCB</p> <p>32A = 03 No Each Fitted with 25A RCCB</p>	No	<b>3</b>
	<p><b><u>IP67 waterproof mobile power supply maintenance box</u></b></p> <p>Fitted with Industrial Sockets/Plus 5No</p> <p>Cable Reel: 100M (6mm, 4C)</p> <p>MCB: 63A, 5No</p>	No	<b>1</b>

**TERMS AND CONDITIONS:**

1. The Items will be delivered at Bettani Oil and Gas Field. The delivery charges to Bettani Oil and Gas Field to be borne by the supplier/ bidder.
2. Both Technical and Financial evaluation will be made on complete Scope of Supply
3. The vendor will be responsible to address any complaints arises in their supplied items for a period of six months from the date of delivery.
4. All the MCCBs and RCCBs must be from Schneider or equivalent reputed company. Certificate of Origin to be provided by vendor at the time of delivery.
5. Delivery of material will be 4 weeks from the placement of PO.
6. Any required technical clarification/details must be cleared before submission of bid. No change in submitted bid will be entertained after bid submission date.
7. The Supplier must provide Catalogue/ Broachers of the offered MCCBs and RCCBs along with the bid documents and technical evaluation will be carried out on the basis of the these.
8. Material will be accepted after final inspection at site, and payment will be made through Cross cheque thereof.
9. The firm should have valid NTN and GST number and have active status on FBR website.
10. The Firm should have active Professional tax certificate of concerned Excise office where operating business, all these documents will be submitted as part of Bid.
11. Tax submission Certificate (Annex-C) will be provided along with Invoice
12. BOE, GD or SRO to be submitted along with invoice for Income tax/GST exemption if any.
13. Bid Bond Worth Rs. 50,000/- in favor of Field Manager Bettani Oil and Gas Field will be submitted along with the bid.