



**OIL AND GAS DEVELOPMENT COMPANY LIMITED**  
**BETTANI OIL & GAS FIELD**

**TENDER NO. TE/BOGF/Elect-06/2024**

Tender Documents for Procurement of Explosion Proof Flood Lights for extended Condensate Storage Area at BOGF

S/No	Description	A/U	Qty
1	<p><b>Explosion Proof Floodlight:</b> CZ0878d-N250W25-B Ex mark: Ex db eb op is IIB T3 Gb Ex tb op is IIC T150°C/T165°C Db Intended use: Can be used in zone 1, zone 2, zone 21 and zone 22 Ambient temperature: -20°C to +40°C/+55°C Degree of protection: IP66 Rated voltage: 220V AC 50 Hz Power: High pressure sodium vapor lamp 250W Terminal: L1,N, cage type terminal 2x1.5-10mm<sup>2</sup>, PE terminal:2x2.5-6mm<sup>2</sup> Cable entry: Molded plastic 1xM25x1.5 cable gland, diameter: 8-17mm Molded plastic 1xM25x1.5 stopping plug Bracket mounting type</p> <p><b>Or</b> JAA HARVELLS EX ENGLAND TECH ATEX BGG-EX003 POWER: 300W, Input: 220V/50HZ CCT: 6000-6500K Protection: IP65</p> <p><b>Or</b> <b>Equivalent LED Explosion Proof Zone-1 Floodlights</b></p>	No	15

**TERMS AND CONDITIONS:**

1. The Items will be delivered at Bettani Oil and Gas Field. The delivery charges to Bettani Oil and Gas Field to be borne by the supplier/ bidder.
2. Both Technical and Financial evaluation will be made on complete Scope of Supply
3. The vendor will be responsible to address any complaints arises in their supplied items for a period of six months from the date of delivery.
4. Certificate of Origin to be provided by vendor at the time of delivery.
5. Delivery of material will be 4 weeks from the placement of PO.
6. Any required technical clarification/details must be cleared before submission of bid. No change in submitted bid will be entertained after bid submission date.
7. The Supplier must provide Catalogue/ Broachers of the offered units along with the bid documents and technical evaluation will be carried out on the basis of this informative stuff.
8. Material will be accepted after final inspection at site, and payment will be made through Cross cheque thereof.
9. The firm should have valid NTN and GST number and have active status on FBR website.

10. The Firm should have active Professional tax certificate of concerned Excise office where operating business, all these documents will be submitted as part of Bid.
11. Tax submission Certificate (Annex-C) will be provided along with Invoice
12. BOE, GD or SRO to be submitted along with invoice for Income tax/GST exemption if any.
13. Bid Bond Worth Rs. 50,000/- in favor of Field Manager Bettani Oil and Gas Field will be submitted along with the bid.