



OIL & GAS DEVELOPMENT COMPANY LIMITED
PROCUREMENT DEPARTMENT (LOCAL), ISLAMABAD
SCHEDULE OF REQUIREMENT

Material :Pressure Regulator & Repair kits for F.E.C and Turbo Expander of Nashpa Plant.

Due Date:

Tender Enquiry No: **18695/2022**

Bid Bond Value : **RS.120,000/-**

Attachment(if any) : **YES**

EVALUATION WILL BE CARRIED OUT ON FULL PKG.

Sr No	Description	Quantity	Make/Brand offered	Unit	Unit Price (PKR) Inclusive Of All Taxes Except GST	Unit Price (PKR) Inclusive of GST	Total Price (PKR) Inclusive of GST	Delivery Period Offered	deviation from Tender Spec. If Any
1	Pilot Operated Regulator: EZH-1727-6834641, FOR DETAIL SEE ATTACHMENT.	1		Number					
2	Pressure Regulator, Make: CASHCO, Model: 3B6-5367-81080000A, Serial No: 201607E010364, Size: 1", CL600# RF;FOR DETAIL SEE ATTACHMENT.	1		Number					
3	REPAIR KIT FOR 3B6-5367-81080000A ;FOR DETAIL SEE ATTACHMENT.	1		Number					
4	REPAIR KIT FOR D19-1P47-1Q10000YE;FOR DETAIL SEE ATTACHMENT.	1		Number					
5	REPAIR KIT FOR D1C-4P47-4310000YE;FOR DETAIL SEE ATTACHMENT.	1		Number					

Special Note: The prospective bidders also download the master set of Tender Document

- The prospective bidders may keep in touch with OGDCL web site for downloading the clarifications/amendments (if any) issued by OGDCL.
- BID VALIDITY: 180 DAYS FROM TECHNICAL BID OPENING, DELIVERY PERIOD: 120 DAYS AFTER ISSUANCE OF LPO ON FOR NASH PLANT,KPK. PAYMENT TERM: AFTER DELIVERY & INSPECTION.



OIL & GAS DEVELOPMENT COMPANY LIMITED
PROCUREMENT DEPARTMENT (LOCAL), ISLAMABAD
SCHEDULE OF REQUIREMENT

Mandatory Checklist

Please confirm the compliance of the following mandatory information along with the bid(s) (failing which bids(s) will not be accepted)

Documents	To be Attached with the Technical/Financial Bids	Compliance	
		Yes <input type="checkbox"/>	No <input type="checkbox"/>
Original Bid Bond	Technical Bid	Yes <input type="checkbox"/>	No <input type="checkbox"/>
Copy of NTN Certificate	Technical Bid	Yes <input type="checkbox"/>	No <input type="checkbox"/>
Copy of GST Certificate	Technical Bid	Yes <input type="checkbox"/>	No <input type="checkbox"/>
Confirmation that the Firm is appearing on FBR's Active Taxpayer List	Technical Bid	Yes <input type="checkbox"/>	No <input type="checkbox"/>
Duly signed and stamped Annexure-A (Un-priced)	Technical Bid	Yes <input type="checkbox"/>	No <input type="checkbox"/>
Duly filled, signed and stamped Annexure-B	Technical Bid	Yes <input type="checkbox"/>	No <input type="checkbox"/>
Duly filled, signed and stamped Annexure-D	Technical Bid	Yes <input type="checkbox"/>	No <input type="checkbox"/>
Duly filled, signed and stamped Annexure-L on Company's Letterhead	Technical Bid	Yes <input type="checkbox"/>	No <input type="checkbox"/>
Duly signed and stamped Annexure-M on Company's Letterhead	Technical Bid	Yes <input type="checkbox"/>	No <input type="checkbox"/>
Duly signed and stamped Annexure-N on Non-Judicial Stamp Paper duly attested by Notary Public	Technical Bid	Yes <input type="checkbox"/>	No <input type="checkbox"/>
Duly filled, signed and stamped Annexure-A (Priced)	Financial Bid	Yes <input type="checkbox"/>	No <input type="checkbox"/>
Duly filled, signed and stamped Annexure-C	Financial Bid	Yes <input type="checkbox"/>	No <input type="checkbox"/>
Duly filled, signed and stamped Annexure-E	Financial Bid	Yes <input type="checkbox"/>	No <input type="checkbox"/>



OIL & GAS DEVELOPMENT COMPANY LIMITED
PROCUREMENT DEPARTMENT (LOCAL), ISLAMABAD
SCHEDULE OF REQUIREMENT

For the Vendors/Contractors who opt to submit Bank Draft/Call Deposit/Pay order against Bid Bond/Performance Bond, our Accounts Department has finalized an arrangement for online payment to such Vendors/Contractors, which will be processed through (IBFT & LFT) for which following information is required:

i.	IBAN No. (International Bank Account Number 24 Digits)	
ii.	Vendor Name as per Title of their Bank Account	
iii.	Contact No.of Company's CEO/ Owner (Mobile & Landline)	
iv.	Bank Name.	
v.	Bank Branch Name and Code	

Name, Sign and Stamp of the authorized official of the Bidder(s) _____

DETAILS FOR INDENTED ITEMS

Item 1: Pilot Operated Regulator, Type/Model: EZH-1727-6834641 (for SNGPL revert line to provide fuel gas to camp during ATA) Make: Fisher or equivalent in dimensions and functionality.

Type: EZH, Valve Size: NPS 1, Fluid: Fuel Gas, Body Material: WCC Steel, Trim Size: 1 Inch, Rating: CL600, End Connection: RF Flg, Trim Type: Standard, Diaphragm Material: NBR, Disk/Seat Material: NBR, Elastomers: NBR, Pilot Type: PRX/120, Pilot Spring Range: 73 to 123 psig (5 to 8.5 bar), Pilot Diaphragm Material: NBR, Pilot Trim: NBR/SST, Check Valve Option: Yes, Tubing & Fitting Material: SST/Steel, Certificate Type: Conformity, Test and Material, Certificate Description 1: Actual Test Report, Certificate Description 2: Air Test, Seat Leakage, Functional, Certificate Description 3: Sub-Supplier Material Certs - Body Only, Pilot Body Material: Steel, Pilot Spring Case Material: Steel, Pilot Spring Number: M0255220X12, Pilot Spring Color: Black, Max Operating Inlet Pressure: 1500 psig, Max Operating Outlet Pressure: 123 psig, Max Diff Pressure: 1500 psid, Min Diff Pressure: 15.7 psid, Temperature Range: -20 to 180 Deg F.

Item 2: Seal Gas Pressure Regulator for Turbo Expander, Model: 3B6-5367-81080000A Serial No: 201607E010364, Size: 1", CL600# RF HP/CS/CS/S36/HP PDF Range:10-40 PSI, Make: CASHCO or equivalent in dimensions and functionality.

Item 3: Repair Kit P#3B6-536K-BA of CASHCO Regulator 3B6-5367-81080000A at Turbo Expander seal gas regulator, Make: CASHCO or equivalent in dimensions and functionality.

Repair kit Includes the following parts

3.1:	550-69-4-04112-00 HYDRA LOK NUT, 5/8-11-	Qty. =1
3.2:	210-75-1-01271-00 DIAPHRAGM, 0.006; 4.859	Qty. =2
3.3:	295-Z6-5-01283-00 GASKET, 4.865; 4.437	Qty.=2
3.4:	A60-80-6-E1017-00 PISTON, HP 345	Qty.=1
3.5:	195-80-4-01052-00 CYLINDER, HP & 345	Qty.=1
3.6:	830-78-5-06463-00 SPRING, ID=0.250 P=	Qty.=1
3.7:	295-Z6-5-04037-00 GASKET, 0.875; 0.625;	Qty.=1
3.8:	725-96-5-00754-00 O-RING -220, 1.375; 1.625	Qty.=1
3.9:	726-96-5-02507-00 QUARD RING -012, 0.375;	Qty.=1
3.10:	720-89-5-00120-00 BACKUP RING -012	Qty.=1
3.11:	295-Z6-5-00728-00 GASKET, 1.615; 1.383	Qty.=1

Item 4: Repair Kit P# D19-1P4K-AE of CASHCO regulator D19-1P47-1Q10000YE at Fuel Gas System of FEC Compression plant - Tag: PCV-2914, Make: CASHCO or equivalent in dimensions and functionality.

Repair kit Includes following part#

4.1:	790-BK-5-P0197-00 SEAT, 2" DA	QTY=01
4.2:	725-95-5-P9121-00 O-RING -121, 1.062; 1.250;	QTY=03
4.3:	210-95-4-P0148-14 DIAPHRAGM, 0.074;	QTY=01
4.4:	725-95-5-P9149-00 O-RING -149, 2.812; 3.000;	QTY=01
4.5:	725-95-5-P9227-00 O-RING -227, 2.125; 2.375;	QTY=01

Item 5: Repair Kit P# D1C-4P4K-AE of CASHCO regulator D1C-4P47-4310000YE at Starting Air System of FEC Compression plant - Tag: PCV-2911, Make: CASHCO or equivalent in dimensions and functionality.

Repair kit Includes following Part#:

5.1:	210-95-4-P0148-06 DIAPHRAGM, 0.074	Qty:01,
5.2:	790-BK-5-P0433-00 SEAT, 3" & 4" DA	Qty:01,
5.3:	725-95-5-P9254-00 O-RING -254, 5.500; 5.750;	Qty:01,
5.4:	725-95-5-P9124-00 O-RING -124, 1.250; 1.437	Qty:03,
5.5:	725-95-5-P9425-00 O-RING -425, 4.500; 5.000;	Qty:01

TERM AND CONDITION

- 1- MANUFACTURER MUST HAVE 15 YEARS OF THE MANUFACTURING OF SUCH TYPE OF ITEMS.
- 2- BIDDER MUST PROVIDE AT LEAST 3 REFERENCES WITH E-MAIL ADDRESS OF ALREADY SUPPLIED SUCH MATERIAL AT PLANTS.
- 3- BIDDER / MANUFACTURER MUST PROVIDE THE CALIBRATION AND MATERIAL TEST CERTIFICATE WITH MATERIAL.
- 4- MATERIAL MUST HAVE THE STANDARD OEM WARRANTY/GUARANTEE.
- 5- BIDDER MUST CONFIRM THAT QUOTED ITEMS ARE 100% FIT IN SPECIFICATION, SIZE AND FUNCTION/METALLURGY FOR THE MODEL/PART NOS. MENTIONED BY OGDCL.
- 6- IN CASE 'EQUIVALENT' MAKE & MODEL AGAINST SPECIFIED ITEMS ARE OFFERED CONFIRMATION CERTIFICATE FROM OEM SHOULD BE PROVIDED THAT "OFFERED ITEMS AND THEIR MAKE, MODEL ARE EXACTLY FUNCTIONAL REPLACEMENT OF SPECIFIED ITEMS IN ALL ASPECTS OF SPECIFICATIONS, SIZE, INSTALLATION AND FUNCTIONALITY.
- 7- OFFERED MATERIAL MUST BE NEW & FREE FROM ANY DEFECT.