



PROCUREMENT DEPARTMENT (LOCAL), ISLAMABAD
SCHEDULE OF REQUIREMENT

Material :Foam Wiper Balls

Due Date:

Tender Enquiry No: 18782/2022

Bid Bond Value : RS.100,000/-

Attachment(if any) : YES

EVALUATION WILL BE CARRIED OUT ON FULL PKG.

Sr No	Description	Quantity	Make/Brand offered	Unit	Unit Price (PKR) Inclusive Of All Taxes Except GST	Unit Price (PKR) Inclusive of GST	Total Price (PKR) Inclusive of GST	Delivery Period Offered	deviation from Tender Spec. If Any
1	FOAM WIPER BALLS, SIZE 125MM, FOR WIPE/CLEAN ID OF DRILL PIPES FROM CEMENT,MUD,BRINE/DEBRIS	100		Number					
2	FOAM WIPER BALLS, SIZE 150MM, FOR WIPE/CLEAN ID OF DRILL PIPES FROM CEMENT,MUD,BRINE/DEBRIS.	100		Number					

Special Note: The prospective bidders also download the master set of Tender Document

- The prospective bidders may keep in touch with OGDCL web site for downloading the clarifications/amendments (if any) issued by OGDCL.
- BID VALIDITY:180 DAYS FROM TECHNICAL BID OPENING,DELIVERY PERIOD: 120 DAYS AFTER ISSUANCE OF LPO. PAYMENT: AFTER DELIVERY & INSPECTIONS.



OIL & GAS DEVELOPMENT COMPANY LIMITED
PROCUREMENT DEPARTMENT (LOCAL), ISLAMABAD
SCHEDULE OF REQUIREMENT

Mandatory Checklist

Please confirm the compliance of the following mandatory information along with the bid(s) (failing which bids(s) will not be accepted)

Documents	To be Attached with the Technical/Financial Bids	Compliance	
		Yes <input type="checkbox"/>	No <input type="checkbox"/>
Original Bid Bond	Technical Bid	Yes <input type="checkbox"/>	No <input type="checkbox"/>
Copy of NTN Certificate	Technical Bid	Yes <input type="checkbox"/>	No <input type="checkbox"/>
Copy of GST Certificate	Technical Bid	Yes <input type="checkbox"/>	No <input type="checkbox"/>
Confirmation that the Firm is appearing on FBR's Active Taxpayer List	Technical Bid	Yes <input type="checkbox"/>	No <input type="checkbox"/>
Duly signed and stamped Annexure-A (Un-priced)	Technical Bid	Yes <input type="checkbox"/>	No <input type="checkbox"/>
Duly filled, signed and stamped Annexure-B	Technical Bid	Yes <input type="checkbox"/>	No <input type="checkbox"/>
Duly filled, signed and stamped Annexure-D	Technical Bid	Yes <input type="checkbox"/>	No <input type="checkbox"/>
Duly filled, signed and stamped Annexure-L on Company's Letterhead	Technical Bid	Yes <input type="checkbox"/>	No <input type="checkbox"/>
Duly signed and stamped Annexure-M on Company's Letterhead	Technical Bid	Yes <input type="checkbox"/>	No <input type="checkbox"/>
Duly signed and stamped Annexure-N on Non-Judicial Stamp Paper duly attested by Notary Public	Technical Bid	Yes <input type="checkbox"/>	No <input type="checkbox"/>
Duly filled, signed and stamped Annexure-A (Priced)	Financial Bid	Yes <input type="checkbox"/>	No <input type="checkbox"/>
Duly filled, signed and stamped Annexure-C	Financial Bid	Yes <input type="checkbox"/>	No <input type="checkbox"/>
Duly filled, signed and stamped Annexure-E	Financial Bid	Yes <input type="checkbox"/>	No <input type="checkbox"/>



OIL & GAS DEVELOPMENT COMPANY LIMITED
PROCUREMENT DEPARTMENT (LOCAL), ISLAMABAD
SCHEDULE OF REQUIREMENT

For the Vendors/Contractors who opt to submit Bank Draft/Call Deposit/Pay order against Bid Bond/Performance Bond, our Accounts Department has finalized an arrangement for online payment to such Vendors/Contractors, which will be processed through (IBFT & LFT) for which following information is required:

i.	IBAN No. (International Bank Account Number 24 Digits)	
ii.	Vendor Name as per Title of their Bank Account	
iii.	Contact No.of Company's CEO/ Owner (Mobile & Landline)	
iv.	Bank Name.	
v.	Bank Branch Name and Code	

Name, Sign and Stamp of the authorized official of the Bidder(s) _____

ANNEXURE-B

Oil & Gas Development Company Ltd.
Islamabad- Pakistan

Title: Specifications for Foam Wiper Balls

Foam Wiper Balls

1. DESCRIPTION

Foam Wiper Balls should be able to wipe/clean the I.D of drill pipe or tubing strings of cement, fluids or debris. They will be used to separate fluids. Wiper Balls should be made of high quality natural rubber and can be used in a temperature range of 40°F (4°C) to 302°F (150°C). The balls should be able to pass through small restrictions without being damaged. Wiper Balls can be loaded into drill pipe or tubing connections easily passing through internal upset restrictions such as mechanical setting tools, diverters, and liner running tools.

2. SPECIFICATIONS

Sr. No.	Description	150MM	125MM
i	Size	150mm + 2mmt	125mm + 2mmt
ii	Density	160-180 kg/m ³	160-180 kg/m ³
iii	Weight	350g ± 20g	200g ± 20g
iv	Typical Wiping Range	4.75" to 2.00" (120.70mm to 50.8mm)	4.00" to 1.75" (101.6mm to 44.5mm)
v	Minimum Restriction	0.875" (22.2mm)	0.75" (19.1mm)
vi	Material	Natural Rubber	Natural Rubber
vii	Elongation at Break	920%	920%
viii	Tensile Strength	28N/m ²	28N/m ²
ix	Heat/Cold Consistency	+80°C / -40°C	+80°C / -40°C

3. TERMS AND CONDITIONS

- i. Supplier will provide samples (02 nos. of Foam Wiper Balls of each size) along with the technical bid to OGDCL.
- ii. OEM technical specifications, on OEM letter head, to be attached with the technical bid.
- iii. The bid to be submitted through two envelopes one technical and other financial.
- iv. Maximum delivery period of the balls is 12 weeks.
Supplier will clearly mention the differences of specifications if any, with OGDCL specification.