

OIL & GAS DEVELOPMENT COMPANY LIMITED
PROCUREMENT DEPARTMENT, ISLAMABAD
FOREIGN SECTION A

(To be completed, filled in, signed and stamped by the principal)

ANNEXURE 'A'

Material CHARCOAL FILTERS FOR AMINE SWEETENING AND DEHYDRATION PLANT OF DAKHNI
 Tender Enquiry No PROC-FA/CB/P&P-3309/2018
 Due Date
 Evaluation Criteria FULL PKG.

SCHEDULE OF REQUIREMENT

| Sr No | Description | Unit | Quantity | Unit Price (FOB) | Total Price (FOB) | Unit Price C & F BY SEA | Total Price C & F BY SEA | Deviated From Tender Spec. If Any |
|-------|---|--------|----------|------------------|-------------------|-------------------------|--------------------------|-----------------------------------|
| 1 | ELEMENT FILTER, ACTIVATED CARBON, CHARCOAL, LENGTH: 22" AS PER SPECIFICATIONS ATTACHED. | Number | 800 | | | | | |

Handwritten signature and stamp:
 Jelled
 2/11/18
 Dept. Ext: 4136

Note:

1. Bid bond: Pursuant to tender clause # 2.2, 11.4, 13 & 35.3.2, bid(s) must be accompanied by an upfront bid bond in the form of pay order/ demand draft or bank guarantee issued by scheduled bank of Pakistan or a branch of foreign bank operating in Pakistan, for an amount of US\$ 1,500/- (US\$ One thousand five hundred only) or equivalent Pak Rupees, with technical bid and valid for 150 days from the date of opening of the bids. The bank guarantee must be issued in accordance with the format as per Annexure-C of the tender documents.

2. Shipment from ACU member Countries: In case of shipment from ACU member countries, the LC beneficiary should be of that particular country from where the consignment is being shipped.

3. Terms and conditions: Bidders are advised to carefully read all the terms and conditions of the Tender Document available at OGDCL web site in the master tender document.

4. Summary rejection criteria: - The summary rejection criteria at clause 35 of the tender document may also be examined carefully. Any bid not meeting the criteria spelled in the clause # 35 shall be summarily rejected without any right of appeal. The detailed tender document is available on OGDCL website as "Master set of tender document-Foreign".

5. Payment Terms: Clause No: 4 of Section-III (Part-B) i.e. Conditions of Contract "Special" of Tender Document has been amended and following will be the payments methods.

- i. **Tender value less than or equal to US\$ 200,000:** Payment to the Contractor/ bidder in foreign currency shall be made by establishing in favor of the Contractor an irrevocable Letter of Credit (hereinafter called the L/C). 70 % Payment (s) under the L/C will be made for the FOB/ CFR / CPT (as the case may be) price of material of each shipment upon submission of the shipping documents. Balance 30% Payment will be released after receipt, inspection and acceptance of material.

- ii. **Tender value more than US\$ 200,000:** Payment to the Contractor/ bidder in foreign currency shall be made by establishing in favor of the Contractor an irrevocable Letter of Credit (hereinafter called the L/C). 80 % Payment (s) under the L/C will be made for the FOB/ CFR / CPT (as the case may be) price of material of each shipment upon submission of the shipping documents. Balance 20% Payment will be released after receipt, inspection (in addition of pre-shipment inspection) and acceptance of material.

Charcoal filters Specifications

Max Pressure (Strength): 90 PSID

Operating Temperature: 300 degree Fahrenheit

Nominal Dimensions:- Length = 22 inches, Outer Diameter = 11 inches,

Inner Diameter: 1.5 inches (equivalent to PECO 1122 C)

Carbon: Lignite base granular activated carbon

Can body/ Core: Perforated plated carbon steel

Core cover: Cotton

Outer cover: Cotton

Outer Support: Perforated plated steel

Handel: Carbon steel or stainless steel

End Caps: Plated steel

Gaskets: Polymer based

Mesh: 8x30 , Ash content~ 12-15%

Moisture~12%

Molasses Number ~ 350

Iodine Number ~ 625, Abrasion ~ 75

Terms & Conditions:

- 1- The manufacturer should have atleast 10 years of manufacturing experience for charcoal type of filters. Manufacturer having less than 10 year experience will not be considered for technical evaluation.
- 2- Manufacturer/bidder will provide all the relevant documents showing the manufacturing experience, previous supply record and technical brochure in technical bid.
- 3- Bidder/manufacturer to confirm the supply of each charcoal filter in separate packing/canister.
- 4- Bidder to confirm the application of charcoal filters for amine and glycol streams.
- 5- Delivery period: 04 months after LC establishment