

OIL & GAS DEVELOPMENT COMPANY LIMITED
PROCUREMENT DEPARTMENT, ISLAMABAD
FOREIGN SECTION E

(To be completed, filled in, signed and stamped by the principal)

(P: 1/3)

ANNEXURE 'A'

Material EXPLOSION PROOF MOTOR CONTROL STATIONS, JUNCTION BOXES AND CABLE GLANDS FOR DAKHNI PLANT
Tender Enquiry No PROC-FE/CB/P&P/DKN-4488/2019
Due Date
Evaluation Criteria FULL

SCHEDULE OF REQUIREMENT

Sr No	Description	Unit	Quantity	Unit Price (FOB)	Total Price (FOB)	Unit Price C & F BY SEA	Total Price C & F BY SEA	Deviated From Tender Spec. If Any
1	Cable Glands Size M20 Explosion Proof (Complete With Shroud, Lock Nut and Washer), make: STAHL or equivalent in fit form & functionality (detail attached)	Number	100					
2	Cable Glands Size M32 Explosion Proof (Complete With Shroud, Lock Nut and Washer), make: STAHL or equivalent in fit form & functionality (detail attached)	Number	14					
3	Control Relay Model: 11BG0022A Rating: 10 Amp, 2NO+2NC Coil Voltage: 220VAC Make: Lovato or equivalent in fit form & functionality	Number	25					
4	Control Relay Model: 11BG0022D Rating: 10 Amp, 2NO+2NC Coil Voltage: 24VDC Make: Lovato or equivalent in fit form & functionality	Number	25					
5	Explosion Proof Junction Box Size 8'x8'x4' with 02 x M25 plugged openings at bottom and 01xM25 opening at top, 8x4mm ² terminal strips with stoppers + 4mm ² Earth terminal, make: STAHL or equivalent in fit form & functionality(detail attached)	Number	25					
6	Explosion Proof Local Control Station complete in all respect with ampere meter, make: STAHL or equivalent in fit form & functionality (detail attached)	Number	16					
7	Explosion Proof Local Control Station complete in all respect without ampere meter, make: STAHL or equivalent in fit form & functionality (detail attached)	Number	10					

Note:

(P-2/3)

ATTACHEMENT FOR INDENT # DKN-6242 (TE# PROC-FE/CB/P&P/DKN-4488/2019)

S.No.	Detail description
1	Cable Glands Size M20 Explosion Proof (Complete With Shroud, Lock Nut and Washer), suitable for hazardous area Zone 1, Ex II 2 G Ex de IIA T6 Gb, IP 65, suitable for ambient temperature -2 to +55 Degree C, Make: STAHL OR EQUIVALENT (in fit, form & functionality) .
2	Cable Glands Size M32 Explosion Proof (Complete With Shroud, Lock Nut and Washer), suitable for ambient temperature -2 to +55 Degree C, Make: STAHL OR EQUIVALENT (in fit, form & functionality) .
3	Control Relay Model: 11BG0022A Rating: 10 Amp, 2NO+2NC Coil Voltage: 220VAC Make: Lovato OR EQUIVALENT (in fit, form & functionality) .
4	Control Relay Model: 11BG0022D Rating: 10 Amp, 2NO+2NC Coil Voltage: 24VDC Make: Lovato OR EQUIVALENT (in fit, form & functionality) .
5	Explosion Proof Junction Box Size 8'x8'x4' with 02 x M25 plugged openings at bottom and 01xM25 opening above, 8x4mm ² terminal strips with stoppers + 4mm ² Earth terminal, suitable for hazardous area Zone 1, Ex II 2 G Ex de IIA T6 Gb, IP 65, suitable for ambient temperature -20 to +55 Degree C, Make: STAHL OR EQUIVALENT (in fit, form & functionality) .
6	<p>Explosion Proof Local Control Station complete in all respect with ammeter , Make: STAHL OR EQUIVALENT (in fit, form & functionality) , Size : Compact Type , suitable for hazardous area Zone 1 (Ex II 2 G Ex de IIA T6 Gb), Degree of Protection IP: 65, Rated Voltage 230VAC, 50HZ , ambient temperature -20to +55 Degree C, With start push button, emergency stop button mushroom type red color, REMOTE /LOCAL selector switch, HAND /OFF/AUTO selector switch, Enclosure UV/IR resistant, color Black with provision of internal and external Earth , Enclosure consists of following:</p> <p>1- 1 No Push Start Button(Green) with 1 No "N/O" & "1-No "N/C" contact block 2- 1 No Emergency Push button Mushroom Type Red Color (Turn to Reset) with 1-No "N/O" & 1-No "N/C" contact block 3- 1 No Selector switch 2P 16A (1/2) c/w Polymers handle. 4- 1 No Selector switch 2P 16A (1/0/2) c/w Polymers handle. 5- 1 No No. Entries m25 (Bottom) 6- 1 No No Name Tag.</p> <p>Following Ampere meters will be also required within the LCS:</p> <p>1- Ammeter range (75 A), CT ratio (15/1 A), Quantity (02 Nos) 2- Ammeter range (500 A), CT ratio (100/5 A), Quantity (02 Nos) 3- Ammeter range (150 A), CT ratio (30/5 A), Quantity (03 Nos) 4- Ammeter range (1000 A), CT ratio (200/1 A), Quantity (02 Nos) 5- Ammeter range (60 A), CT ratio (30/5 A), Quantity (01 Nos) 6- Ammeter range (250 A), CT ratio (50/1 A), Quantity (02 Nos) 7- Ammeter range (15 A), CT ratio (5/5 A), Quantity (04 Nos)</p>
7	<p>Explosion Proof Local Control Station complete in all respect without ammeter , Make: STAHL OR EQUIVALENT (in fit, form & functionality) , Size : Compact Type , suitable for hazardous area Zone 1 (Ex II 2 G Ex de IIA T6 Gb), Degree of Protection IP: 65, Rated Voltage 230VAC, 50HZ , ambient temperature -20to +55 Degree C, With start push button, emergency stop button mushroom type red color, REMOTE /LOCAL selector switch, HAND /OFF/AUTO selector switch, Enclosure UV/IR resistant, color Black with provision of internal and external Earth , Enclosure consists of following:</p> <p>1- 1 No Push Start Button(Green) with 1 No "N/O" & "1-No "N/C" contact block 2- 1 No Emergency Push button Mushroom Type Red Color (Turn to Reset) with 1-No "N/O" & 1-No "N/C" contact block 3- 1 No Selector switch 2P 16A (1/2) c/w Polymers handle. 4- 1 No Selector switch 2P 16A (1/0/2) c/w Polymers handle. 5- 1 No No. Entries m25 (Bottom) 6- 1 No No Name Tag.</p>

NOTE:

1. **Bid bond:** - Pursuant to tender clause # 2.2, 11.4, 13 & 35.3.2, bid bond amounting to US\$ 580/- (USD Five Hundred and Eighty only) or equivalent in Pak Rupees should be submitted with the technical bid.
2. **Bid Bonds & Performance Bank Guarantees:** List of Banks for Bid Bonds & Performance Bank Guarantees is available in Foreign Tender Document on OGDCL website. Bid Bonds & Performance Bank Guarantees submitted from other than the mentioned Banks are not acceptable.
3. **Information/Documents required:**
 - i. Corporate and Financial Information duly filled-in signed/stamped by Manufacturer & Bidder is required **also available at OGDCL website (Master Set of Press Tender Documents- Foreign)**
 - ii. Beneficiary's Verified certificate of incorporation / valid trade license is required.
 - iii. List of Company's (beneficiary) Directors and Undertaking that Company and its directors are not blacklisted anywhere, is required.
 - iv. Submission of wrong information/documents will be liable to legal proceedings including
4. **Foreign Procurement Payment Terms also available at OGDCL website (Tender Tab)**
5. **Evaluation Criteria:** FULL CONSIGNMENT WISE ON C&F BY SEA KARACHI BASIS.
6. **Shipment from ACU member Countries:** In case of shipment from ACU member countries, the LC beneficiary should be of that particular country from where the consignment is being shipped.
7. **Terms and conditions:-**Bidders are advised to carefully read all the terms and conditions of the Tender Document available at OGDCL website in the master tender document.
8. **Delivery Period:** 120 Days