

OIL & GAS DEVELOPMENT COMPANY LIMITED
PROCUREMENT DEPARTMENT, ISLAMABAD
FOREIGN SECTION E

(To be completed, filled in, signed and stamped by the principal)

ANNEXURE 'A'

Material EXPLOSION PROOF SAFETY FLOOD LIGHTS
Tender Enquiry No PROC-FE/CB/PROD-4609/2020
Due Date
Evaluation Criteria FULL

SCHEDULE OF REQUIREMENT

Sr No	Description	Unit	Quantity	Unit Price (FOB)	Total Price (FOB)	Unit Price C & F BY AIR	Total Price C & F BY AIR	Deviated From Tender Spec. If Any
1	FLOOD LIGHT SAFETY EXPLOSION PROOF 400W, IP65/66, WF2, 220 VAC 50 Hz. COMPLETE WITH HIGH PRESSURE SODIUM LAMP, LIGHT FITTING & ACCESSORIES (DETAIL SPECIFICATIONS ARE ATTACHED AT ANNEX- 1 2.	Number	40					

Note:

1. **Bid bond:** - Pursuant to tender clause # 2.2, 11.4, 13 & 35.3.2, bid bond amounting to US\$ 320/- (USD Three Hundred and Twenty only) or equivalent in Pak Rupees should be submitted with the technical bid.
2. **Bid Bonds & Performance Bank Guarantees:** List of Banks for Bid Bonds & Performance Bank Guarantees is available in Foreign Tender Document on OGDCL website. Bid Bonds & Performance Bank Guarantees submitted from other than the mentioned Banks are not acceptable.
3. **Information/Documents required:**
 - i. Corporate and Financial Information duly filled-in signed/stamped by Manufacturer & Bidder is required also available at OGDCL website (Master Set of Press Tender Documents- Foreign)
 - ii. Beneficiary's Verified certificate of incorporation / valid trade license is required.
 - iii. List of Company's (beneficiary) Directors and Undertaking that Company and its directors are not blacklisted anywhere, is required.
 - iv. Submission of wrong information/documents will be liable to legal proceedings including
4. **Foreign Procurement Payment Terms also available at OGDCL website (Tender Tab)**
5. **Evaluation Criteria:** FULL CONSIGNMENT WISE ON C&F BY AIR ISLAMABAD BASIS.
6. **Shipment from ACU member Countries:** In case of shipment from ACU member countries, the LC beneficiary should be of that particular country from where the consignment is being shipped.
7. **Terms and conditions:**-Bidders are advised to carefully read all the terms and conditions of the Tender Document available at OGDCL website in the master tender document.
8. **Delivery Period:** 2 months



Annexure - Z

DATA SHEET

EXPLOSION PROOF SAFETY FLOOD LIGHT

General

1	Application	Explosion Proof Safety Flood lights for large area lighting in Oil & Gas Fields.
2	Electrical Area Class/Hazardous rating	Class 1, Division 2, Group A, B, C & D
3	Ambient Temperature	upto (+) 55°C
4	Power Rating	400 Watts High Pressure Sodium Safety flood lights, 50 Hz frequency.

Features

5	Light Source	High pressure Sodium Lamp
6	Light source life	Minimum 28000 hours
7	Light output	Minimum 48000 lumens
8	Ballast	Integral Choke ballast for quick start & steady performance.
9	Ignitor	Explosion Proof Ignitor
10	Lens	Thermal shock & impact resistant. One piece lens cover.
11	Mounting	Pole mounting : Trunnion mounting-heavy gauge, hot dip galvanized steel mounting.
12	Rated Voltage	AC 230 V 50Hz/ (200V-240V)
13	Design	Compound Parabolic, double segment
14	Degree of protection	IP65/66
15	Corrosion-Proof Grade:	WF2
16	Explosion-proof	Ex d IIB T3 certified or equivalent

Standard Material

17	Body Material	Copperfree marine-grade aluminum alloy
18	Lens	Tempered glass
19	Reflector	Bright highly polished aluminum
20	Gasket	High Temperature Silicone rubber, firmly seated
21	Socket	Heavy duty porcelain with heavy gauge brass shell.
22	bolts	Stainless steel bolt