



OIL & GAS DEVELOPMENT COMPANY LIMITED

REQUEST FOR QUOTATION (FOREIGN)

OGDCL House, Jinnah Avenue, Islamabad Pakistan

Description: Procurement of 9-5/8" & 7" Casing

Tender Enquiry No: PROC-FB/CB/D-6200000019/22

Delivery Period: 6 Months CFR by SEA after LC Establishment

Evaluation Criteria: Each Group Wise

Bid Bond Value: USD 60,000/- for Group A and USD 7,500/- for Group B equivalent PAK Rupees must be submitted with technical bid with validity of 120 days beyond opening date.

Bid Validity: 60 Days from technical bid opening date

Bidding Procedure: Single Stage Two Envelope. Master set of Tender Document is available on OGDCL's Website

Purchase Req: 20000181

Attachments: Yes

SR NO	Group	Material Description	Unit	Quantity	Unit Price (USD) (FOB)	Total Price (USD) (FOB)	Unit Price (USD) (CFR)	Total Price (USD) (CFR)	Deviation From Tender Spec. If Any
1.	A	CASING SMLS API 5CT 9-5/8" 47# L80,13 CH MODIFIER SMLS STANDARD API 5CT NOMINAL SIZE 9-5/8" WEIGHT PER FT 47# GRADE L80,13 CHROME THREAD CAL-IV TESTED CONNECTION SOUR CERTIFICATION PSL-3. As per detailed description attached	Meter	2,500					
2.	A	CASING SMLS API 5CT 9-5/8" 47# L80,13 CH MODIFIER SMLS STANDARD API 5CT NOMINAL SIZE 9-5/8" WEIGHT PER FT 47# GRADE L80,13 CHROME THREAD CAL-IV TESTED CONNECTION SOUR CERTIFICATION PSL-3. As per detailed description attached	Meter	2,500					

retted
13/10/2022

3.	B	CASING SMLS API 5CT 7" 32# L80,13 CHROME MODIFIER SMLS STANDARD API 5CT NOMINAL SIZE 7" WEIGHT PER FT 32# GRADE L80,13 CHROME THREAD CAL-IV TESTED CONNECTION SOUR CERTIFICATION PSL-3. As per detailed description attached	Meter	1,000					
----	---	--	-------	-------	--	--	--	--	--

vetted

*Thomas
13/01/22*

DETAIL DESCRIPTION, SCHEDULE OF REQUIREMENT (SOR)

GROUP-A

1. 9-5/8" OD, SEAMLESS STEEL CASING PIPE CONFORMING TO API SPECS 5CT, 10TH EDITION, GRADE L-80, 13 CHROME, WEIGHT 47 LBS/FT, VAM21/TSH BLUE OR EQUIVALENT CAL-IV THREAD CONNECTION, PSL-3 R-3 COUPLED WITH SURFACE TREATMENT WITH COPPER PLATING AND WITH PLASTIC TYPE CLOSED END THREAD PROTECTORS ON BOTH ENDS. PROPER COLOUR CODING ON COUPLING FOR GRADE IDENTIFICATION AND WITH OUTSIDE COATING FOR RUST PROTECTION DURING TRANSIT (DRIFT 8-1/2" BIT). DELIVERY TOLERANCE -3 % IN QTY.

QUANTITY = 5,000 METERS.

GROUP-B

2. 7" OD, SEAMLESS STEEL CASING PIPE CONFORMING TO API SPECS 5CT, 10TH EDITION, GRADE L-80, 13 CHROME, WEIGHT 32 LBS/FT, VAM21/TSH BLUE OR EQUIVALENT CAL-IV THREAD CONNECTION, PSL-3, R-3 COUPLED WITH SURFACE TREATMENT WITH COPPERPLATING AND WITH PLASTIC TYPE CLOSED END THREAD PROTECTORS ON BOTH ENDS. PROPER COLOUR CODING ON COUPLING FOR GRADE IDENTIFICATION AND WITH OUTSIDE COATING FOR RUST PROTECTION DURING TRANSIT (DRIFT 6" BIT). DELIVERY TOLERANCE -3 % IN QTY.

QUANTITY = 1,000 METERS.



ALI IFTIKHAR
Manager (DMP)
Ext: 3724




MUHAMMAD USMAN
S.E (DMP)
Ext: 2308





MUHAMMAD YUNUS
A/General Manager(DO)
Ext: 3711


GENERAL TERMS & CONDITIONS

1. Bidders have to submit quoted Manufacturer plant/plants API 5CT PSL-3 (One/Single Manufacturer of casing pipe and threading plant) latest valid & back certificates consecutively (no breaks will be acceptable) from January 2010. (In this regard published API composite List of January 2010 will be considered as reference). Processor of casing pipes will not be considered as casing pipe manufacturer.
2. Data/Specs sheets of quoted casing pipes as per manufacturer standard to be provided by the bidder/manufacturer.
3. The Tensile, Burst, Collapse & compression rating of the Quoted Premium Thread Connection must be equal to or exceed those of the Pipe body ratings. Documents supporting the requirement should be provided along with the bid.
4. All offered thread & coupled premium connections must be CAL-IV certified for offered Casing pipes. In this regards manufacturer to provide confirmation of quoted connection being CAL-IV tested on its letter head along with detailed CAL-IV test report as per ISO 13679:2002/2019 / API 5C5 2002/2017.
5. Delivery allowance of +0 & -3% for Casing Pipes can be allowed, however the payment will be made as per the actual meterage of casing supplied. More than -3 % delivery allowance is not acceptable.
6. Casing Pipes should be provided with mills protective coating on the outside.
7. The casing pipes & casing accessories must be brand new & un-used. Confirmation to this effect is required in the technical offer.
8. The successful bidder will be required to furnish mill inspection certificates for casing pipes with shipping documents. Confirmation to this effect must be provided in the technical offer.
9. Letter in original from the manufacturer(s) covering Warranty/Guarantee for a period of 1-1/2 year from date of shipment for the quoted casing pipes to be submitted with the technical Bid.
10. Authority letters in original from the manufacturer(s) to bidder and from bidder to local agent for offered casing pipes with tender enquiry number to be furnished with the technical offer. The authority letter must be on company letter head, showing the name and contact details (E-mail & fax number) of the signing authority.
11. Original brochure (both hard & soft copy) of the manufacturer(s) containing technical literature / specs sheets specifying physical / performance properties of quoted casing pipes to be submitted with the technical offer.
12. The Casing pipes manufacturer must have manufactured & supplied seamless steel Casing pipes to internationally renowned E & P companies (not belonging to the manufacturer's own country) in excess of 20,000 Meters each year during the last Ten (10) years. The supply record must confirm this fact. The supply record should include only the sales record for offered casing pipes during each year.
13. If the Manufacturer has not already supplied the quoted casing pipes to OGDCL then Manufacturer/Bidder to submit 10 unpriced copies of different Purchase orders against each quoted item sold to 10 different E & P companies mentioned above (not belonging to the manufacturer's own country). Casing Pipes sold to supply / trading houses & services companies etc are not acceptable.
14. If the bidder/Manufacturer has not already supplied offered Casing Pipes to OGDCL then 05 Nos certificates of satisfactory performance for each quoted casing pipes issued by


MUHAMMAD USMAN
S.E (DMP)
Ext: 2308


ALI IFTIKHAR
Manager (DMP)
Ext: 3724


MUHAMMAD YUNUS
A/General Manager(DO)
Ext: 3711


Muhammad Aamir Salim
E.D(Petroserv)
Ext: 3503

authorized officials of at least 5 different internationally renowned E & P companies (not belonging to the manufacturer's own country) must be provided with the technical bid. Certificates issued by supply/Trading houses & service companies etc. will not be considered.

15. Third party inspection (TPI) by internationally reputed inspection company is required as per oil industry practice. OGDCL will arrange inspection during manufacturing and before shipment of the consignment. Bidder/manufacturer will provide full assistant to Inspection Company during inspection. Bidder to confirm that third party inspection report verified by OGDCL will be provided with the shipping documents for LC encashment.


Scope of work for TPI will be as follows but will not be limited to this.


- Full body ultrasonic inspection where applicable.
- Visual thread inspection.
- Full body API drift.
- Verification of mill test certificate.
- Pre-shipment inspection to confirm that shipment is as per Issued PO w.r.t quantity, Packing, Specifications, brand new & unused, weight, length, thread protectors, coating etc.

16. Evaluation criteria is each Group Wise.


17. Delivery time required is 06 Months C&F by sea Karachi after LC opening. Bids delivery exceeding 06 months will be rejected.

18. Bidder to submit complete bid including all above mentioned documents attached.


MUHAMMAD USMAN
S.E (DMP)
Ext: 2308


Muhammad Amir Sana
E.D(Petroserv)
Ext: 3503


ALI IFTIKHAR
Manager (DMP)
Ext: 3724


MUHAMMAD YUNUS
A/General Manager(DO)
Ext: 3711