

OIL & GAS DEVELOPEMNT COMPANY LIMITED

REGIONAL OFFICE, HYDERABAD

Dated: 10/03/2021

1. SORs /SCOPE OF WORK :

SCHOOL FURNITURE REQUIREMENT :

1.	<u>Wooden Dual desks</u>	3x2.5	ft	(Total Quantity 55)
2.	<u>Wooden Class Table</u>	4x2	ft	(Total Quantity 10)
3.	<u>Wooden School chairs</u>	3x1.5	ft	(Total Quantity 20)
4.	<u>Wooden School Benches</u>	6x1	ft	(Total quantity 60)

2. CIVIL WORK REQUIRED IN SCHOOLS BUILDINGS:

- i. Minor repairing/renovation/coloring work in 05 class Rooms at Village Darya Khan Nahyoon

GBPS District Hyderabad.

- ii. Minor repairing/renovation/coloring work in 02 class Rooms and Viranda with repair of wooden doors/windows at Village Haji Ismail Lakho

GBPS District Hyderabad.

- iii. Minor repairing/renovation/colouring work in 02 class Rooms and Viranda with repair of wooden doors/windows at Village Jam Mahar,

GBPS District Hyderabad.

- iv. Minor repairing/renovation/colouring work in 02 class Rooms and Verandah with repair of wooden doors/windows at Village Haji Palyo Khoso

GGPS District Hyderabad.

Abstract of Cost & Quantity

Paint work of Govt. Primary School Building & Construction of New Boundary wall at Haji Darya Khan Nahyo

Sr. No	Description	MES (SOR)	Quantity	Unit
1	S&A 02 coats Distemper with Poly Vinyl Distemper or equivalent, on new or old surface as per instructions of Engineer Incharge	15-06 + 15-07.	244.14	SQM
2	S&A 02 coats of Weather resistant oaint on exterior walls as per attached drawing & instructions of engineer incharge.	15-90 + 15-91	270.84	SQM
3	S&A 02 Coats of Synthetic Enamel Pain painting on new or old surfaces, Steel Chowkat, etc complete in all respect as per instructions of Engineer Incharge	15-60 + 15-61.	38.85	SQM
				Total


BARKAT ALI
CSR OFFICER
(OGDCL) R.O Hyderabad

Abstract of Cost & Quantity


Repair / Maintenance of Govt. Primary School Jamal Mahar

Sr. No	Description	MES (SOR)	Quantity	Unit
1	Hacking cement plaster of walls or lathing, racking out joints when required or racking out cement jointing to walls roofs or floors any description or hacking out concrete to form key or dismantling, lathing without plaster and Loading, Transporting, Unloading & Safe Disposal of dismantled material of at an unobjectionable place outside complete in all respect as per instruction of Engineer Incharge	13-19.	246.51	SQM
2	S&A 19 mm thick Cement Sand double plaster in 1:4 using Sand aggregate from Bolhari on walls, ceiling, etc finished complete in all respect as per instructions of Engineer Incharge	13-11.	239.45	SQM
3	P&L PCC 1:2:4 using crushed or broken stone Petaro / Nooriabad in building all required places / members, complete in all respect as per instructions of engineer incharge.	03-10.	9.05	CUM
4	S&A 02 coats Distemper with Poly Vinyl Distemper or equivalent, on new or old surface as per instructions of Engineer Incharge	15-06 + 15-07*2	254.79	SQM
5	S&A 02 coats of Weather resistant oaint on exterior walls as per attached drawing & instructions of engineer incharge.	15-90 + 15-91*2	377.67	SQM
6	S&A 02 Coats of Synthetic Enamel Pain painting on new or old surfaces, Steel Chowkat, etc complete in all respect as per instructions of Engineer Incharge	15-60 + 15-61*2	52.79	SQM
7	S/F Steel Grill Door (Size 4ft x 7ft) & Main Steel Gate (Size 8ft x 6ft) with OGDCL logo on both pannels as per instructions of engineer incharge.	MR	165.00	Kg
				Total E

BAR

Repair / Maintenance of Govt. Primary School Haji Ismail Lak

Sr. No	Description	MES (SOR)	Quantity	Unit
1	Hacking cement plaster of walls or lathing, racking out joints when required or racking out cement jointing to walls roofs or floors any description or hacking out concrete to form key or dismantling, lathing without plaster and Loading, Transporting, Unloading & Safe Disposal of dismantled material of at an unobjectionable place outside complete in all respect as per instruction of Engineer Incharge	13-19.	296.68	SQM
2	S&F of steel wire neting with steel nails, tie wire in ceiling for cement snad plaster complete in all respect as per instructions of Engineer Incharge	MR	88.31	SQM
3	S&A 19 mm thick Cement Sand double plaster in 1:4 using Sand aggregate from Bolhari on walls, ceiling, etc finished complete in all respect as per instructions of Engineer Incharge	13-11.	341.15	SQM
4	P&L PCC 1:2:4 using crushed or broken stone Petaro / Nooriabad in building all required places / members, complete in all respect as per instructions of engineer incharge.	03-10.	6.21	CUM
5	S&A 02 coats Distemper with Poly Vinyl Distemper or equivalent, on new or old surface as per instructions of Engineer Incharge	15-06 + 15-07*2	244.42	SQM
6	S&A 02 coats of Weather resistant oaint on exterior walls as per attached drawing & instructions of engineer incharge.	15-90 + 15-91*2	326.27	SQM
7	S&A 02 Costs of Synthetic Enamel Pain painting on new or old surfaces, Steel Chowkat, etc complete in all respect as per instructions of Engineer Incharge	15-60 + 15-61*2	106.32	SQM
				Total




RAR

Abstract of Cost & Quantity

Paint work of Govt. Primary School Building & Construction of New Boundary wall at Haji Darya Khan Nahyo

Sr. No	Description	MES (SOR)	Quantity	Unit
1	S&A 02 coats Distemper with Poly Vinyl Distemper or equivalent, on new or old surface as per instructions of Engineer Incharge	15-06 + 15-07.	244.14	SQM
2	S&A 02 coats of Weather resistant oaint on exterior walls as per attached drawing & instructions of engineer incharge.	15-90 + 15-91	270.84	SQM
3	S&A 02 Coats of Synthetic Enamel Pain painting on new or old surfaces, Steel Chowkat, etc complete in all respect as per instructions of Engineer Incharge	15-60 + 15-61.	38.85	SQM
				Total


BARKAT ALI
CSR OFFICER
(OGDCL) R.O Hyderabad