



**OIL AND GAS DEVELOPMENT COMPANY LIMITED
NASHPA OIL & GAS FIELD**

Date: 04-03-2021

SCHEDULE OF REQUIREMENT

TENDER ENQUIRY # TE/NOF/PF/02/2021

Sand blasting, FRP coating and recalibration of crude oil storage tank # 6 at Nashpa

S#	Description	Reference #	Rate	Total rate (inclusive of all Taxes)	Deviation
1	<p>1-Removal of old FRP coating, Sand blasting, New FRP coating of crude oil storage tank # 6 at Nashpa</p> <p>(Capacity=20,000 BBLs, Size = 60' dia x 40' height)</p> <p>Shell = up to 2 M height</p> <p>Floor = complete</p> <p>FRP coating thickness = 3 mm</p> <p>i. One coat of red oxide 2 pack epoxy primer at 50 microns dft</p> <p>ii. Profile all discontinuities with an epoxy putty</p> <p>iii. Two coats of solvent free epoxy resin chopped strand mat coating.</p> <p>iv. One coat of solvent free epoxy and surfacing tissue</p> <p>v. One coat of solvent free epoxy sealer coat</p> <p>2-Calibration of tank along with provision of soft/hard copies of Dip charts</p>				

TERMS AND CONDITIONS:

1. All the material and equipment for removal of old FRP coating, sand blasting, new FRP coating and calibration of tanks will be provided by the contractor. No delivery charges will be paid to the supplier/ bidder.
2. The contractor will provide detail specifications, code, make, origin of material, procedure and job completion schedule for said assignments in Bid.
3. Local material is not acceptable. Resin & other material should be European/USA made. OGDCL has full right to reject the bid if code, specifications or make is not found as per standard/requirement.
4. Any required technical clarification/detail regarding material to be supplied must be cleared before submission of bid. No change in submitted bid will be entertained after bid submission date.
5. Technical & Financial evaluation will be made on the complete scope of supply.
6. The material must be supplied within 02 weeks from the date of PO placement.
7. Certificate of Origin to be provided by vendor at the time of delivery.
8. Material will be accepted after final inspection at site.
9. Payment will be made through Cross Cheque after completion of assignment and acceptance by the inspection team of NOF. No advance payment will be made in this regard.
10. The contractor will give the guarantee of FRP coating for a period of five years.
11. The contractor will provide soft/hard copies of dip charts.
12. The firm should have valid NTN and GST number and have active status on FBR website.
13. The Firm should have active Professional tax certificate of concerned Excise office where operating business and same to be submitted along with the bid.
14. Tax submission Certificate (Annex-C, submitted status) should be provided along with Invoice.
15. BOE, GD or SRO to be submitted along with invoice for Income tax/GST exemption if any.
16. The supplier should have 10 years of prior experience of working at crude oil storage tanks.
17. The contractor will have to make accommodation & food arrangements for the crew with his own resources.