



**OIL AND GAS DEVELOPMENT COMPANY LIMITED
NASHPA OIL & GAS FIELD**

SCHEDULE OF REQUIREMENT

TENDER ENQUIRY # TE/NOF/M/04/2021

Procurement of Procurement of Pipe Fittings for Nashpa Plant

S#	Description	Reference #	Rate	Total rate (inclusive of all Taxes)	Deviation
1	As per attached list				

List of Material Required

SR NO	SIZE	DESCRIPTION	SCH.	RATINGS/ CLASS	STANDARD	MATERIAL	UNIT	Required Qty
1	1"	GATE VALVE SW		1500#	ISO 15761	Body: ASTM A105N Bolting: Hot Dip Galvanized plated Stem: Type 316 S.S. Packing: Mfr. Std. Seats: Hard Faced Type 316 S.S.	NO.	20
2	1"	PIPE NIPPLE PE - NPT (ONE SIDE) L = 4"	160		ASME B36.10M	ASTM A 106-B	NO.	20
3	1"	PIPE NIPPLE PE L= 4"	160		ASME B36.10M	ASTM A 106-B	NO.	20
4	1"	END CAP NPT		CLASS 6000	ASME B16.11	ASTM A 105		20
5	8" X 1"	SOCKOLET		CLASS 6000	ASME B16.11	ASTM A 105	NO.	20
6	8"	ELBOW 90` BW	80		ASME B16.9	ASTM A234 Gr. WPB	NO.	90
7	8"	ELBOW 90` BW (Short Radius)	80		ASME B16.9	ASTM A234 Gr. WPB	NO.	1
8	8"	FLANGE RF, WN	80	600#	ASME B16.5	ASTM A 105	NO.	8
9	8"	GASKET (SPIRAL WOUND)		600#	ASME B16.20	4.45mm THK.SPIRALWOUND 304SS RING 304 SSWINDING, FLEXIBLE GRAPHITE	NO.	32

10	8"	EQUAL TEE BW	80			ASTM A 105	NO.	10
11	8"	RING GASKET RTJ R-49		R-49		SS 316	NO.	17
12	8"	SPECTACLE BLIND RF		600#			NO.	8
13	10" X 8"	CON. REDUCER BW	80		ASME B16.9	ASTM A234 Gr. WPB	NO.	4
14	8"	ELBOW 45` BW	80		ASME B16.9	ASTM A234 Gr. WPB	NO.	4
15	M30	STUD L = 195/NUT				STUDS: ASTM A193 Gr. B7, Hot Dip Galvanized plated NUTS: ASTM A194 Gr. 2H, Heavy Hex, Hot Dip Galvanized plated	NO.	250
16	M30	STUD L = 260/NUT				STUDS: ASTM A193 Gr. B7, Hot Dip Galvanized plated NUTS: ASTM A194 Gr. 2H, Heavy Hex, Hot Dip Galvanized plated	NO.	115

TERMS AND CONDITIONS:

1. Bid submission: single envelope, 1 stage.
2. Evaluation criteria: full consignment wise.
3. The material will be delivered at Nashpa Oil Field. The delivery charges to Nashpa Oil Field to be borne by the supplier/ bidder.
4. MTC of the material along with valid heat number must be provided.
5. Any required technical clarification/detail regarding material to be supplied must be cleared before submission of bid. No change in submitted bid will be entertained after bid submission date.
6. Gaskets of renowned brands like / equivalent to Flexitallic must be quoted.
7. Technical & Financial evaluation will be made on the complete scope of supply.
8. The material must be supplied within 04 weeks from the date of PO placement.

9. Any material found rusted or having poor quality will be rejected and supplier is liable to supply the same within 03 days
10. Certificate of Origin to be provided by vendor at the time of delivery.
11. Material will be accepted after final inspection at site, and payment will be made through Cross cheque thereof.
12. The firm should have valid NTN and GST number and have active status on FBR website.
13. The Firm should have active Professional tax certificate of concerned Excise office where operating business and same to be submitted along with the bid.
14. Tax submission Certificate (Annex-C, submitted status) should be provided along with Invoice.