

OIL AND GAS DEVELOPMENT COMPANY LIMITED
SEISMIC PARTY-2
C/O MANAGER TCS OFFICE SACHAL COLONY LARKANA

Technical Specification and Requirement Details

Lube oil name	Delo gold ultra
Grade	SAE 15W-40 API CI-4
Recommended for	4-Stroke Diesel Engine turbocharged or naturally aspirated
Applications	(1) VOLVO Penta TAD-1341GE-B Diesel Genset 300 KVA (2) Perkins P50-3 Genset (Recorder) (3) Diesel Engine TOYOTA 2KD-FTV (VIGO CHAMP 4X4)
Oil capacities	(1) VPL 38 L (2) Perkins 7 L (3) VIGO 7 L
Required for	2 years
No of equipment's	(1) VPL 1 No (2) Perkins 1 No (3) VIGO 8 Nos Vehicles
Requirement per year	(1) VPL $38 \times 12 = 456$ L/year (2) Perkins $7 \times 12 = 84$ L/year (3) VIGO $7 \times 12 = 84$ L $8 \times 84 = 672$ L
Total required quantity	1212 L or 06 Drums of oil $\times 2 = 12$ drums
Drum capacity	208 Liters
Service intervals	(1) VPL 250 Hrs approx 1 service carried out each month. (2) Perkins 150 Hrs approx 1 service carried out each month. (3) VIGO 2500 Kms approx 1 service carried out each month.
Product code	500574
Viscosity Index	137
Density @ 15 Kg/L	0.872
Base No	10 mg KOH/g
Kinematic viscosity @40°C	115
Kinematic viscosity @100°C	15.10

OIL AND GAS DEVELOPMENT COMPANY LIMITED
SEISMIC PARTY-2
C/O TCS OFFICE SACHAL COLONY LARKANA

TERMS AND CONDITIONS:

1. The supplier should have minimum 5 years of experience.
2. Delivery period for supply is 10 working days after PO issuance
3. Single stage, single envelop bidding will be take place at base camp SP-2 behind cadet college Larkana, Dokri/Mohenjo-Daro Distt Larkana on the date as mention in the tender notice. In case of single bidder tender can be cancelled.
4. The pay order amount of RS. 150,000.00 (Rs one hundred fifty thousand only) in the favor of “Oil and Gas Development Company Limited” as a security deposit/Performance bond must be submit with quotation. Deposit of successful bidder will be retained and refunded after the completion of job. Rest of bid bonds of unsuccessful bidders will be released, immediately
5. Inspection may be carried out at OGDCL base camp and after successful inspection of material it will be accepted.
6. Payment will be made through online bank transfer or cross cheque after complete delivery, inspection and Annex-C submitted by the vendor.
7. Original Equipment Manufacturer backed Warranty / Guarantee
8. Any damage / leak drum will have to be replaced by the vendor without any extra charges.
9. Supplier have to provide all necessary documents i.e. Annex-c, active tax payer certificate with invoice.
10. Bidder should submit complete acceptance of OGDCL TOR.
11. OGDCL reserves the right to annul the case without any reason.
12. Price should be inclusive of all applicable taxes.
13. Bid will be open at Base Camp Seismic Party-2 behind cadet college Larkana, Dokri Distt Larkana on dated at 02.00 PM
14. OGDCL has the right to reject whole shipment or such parts if inspection committee found any counterfeit material or unbranded item
15. Any information regarding tender may be obtained from admin office via email address or telephone

party.chiefsp2@ogdcl.com

+92 51 9225011

+92 51 2623082

+92 330 6360341