

SPECIFICATIONS & QUANTITY

S #	Item	Description	Unit	QTY
1	CCTV -PTZ Camera IP	4-inch 4MP 25X Powered by Dark Fighter IR Network Speed Dome, Focuses on human and vehicle targets classification based on deep learning, Support face capture, 1/2.8" progressive scan CMOS, Powered-by-Dark Fighter technology, 25× optical zoom and 16× digital zoom, up to 100 m IR distance, Support H.265+/H.265 video compression, Color: 0.005 Lux @ (F1.6, AGC ON), 120 dB WDR, Digital defog, BLC, HLC, 3D DNR, Built-in memory card slot, IP66.	Each	3
2	CCTV-Bullet-Camera-IP	DS-2CD1643G0-1ZS/UK 2.8 mm to 13 mm Verifocal Network Bullet Camera (06 explosion proof+03 still bullet)	Each	9
3	NVR -16 Channel	16-ch NVR, 16-ch IP Camera Input, 160 Mbps Incoming Bandwidth, 80 Mbps Outgoing Bandwidth, 1 HDMI/VGA Output Interface, 1-ch Audio Output, Upto 8MP Recording Resolution, H.265+ Decoding Format, 1 SATA Interfaces, 2 USB Interfaces, 1U chassis.	Each	1
4	POE Switch	8 Port Gigabit Unmanaged POE Switch, 8 × Gigabit PoE ports, 1 × Gigabit RJ45 port, 1 × Gigabit SFP fiber optical port, IEEE 802.3at/af standard, MAC Address Table : 4 K, Switching Capacity : 20 Gbps, Packet Forwarding Rate :14.88 Mpps, Internal Cache : 1.5 Mbits, 6 KV surge protection for PoE ports, PoE power management, Gigabit network access, Wire-speed forwarding and non-blocking design, Store-and-forward switching, Solid high-strength metal shell, Reliable fan-free design	Each	8
5	OFC	2 Core Fiber Optic Cable-Shielded Out Door	Meter	680
6	Ethernet Cable	UTP CAT6 Cable, 23 AWG, 305m/1000 Feet Spool, Excellent transmission performance using solid copper, Great PVC flame resistance	Roll	1
7	HDD WD 8TB	Western Digital 8TB WD Purple Surveillance Internal Hard Drive HDD - SATA 6 Gb/s, 128 MB Cache, 3.5",5640 rpm, 128 MB buffer.	Each	1
8	Steel Pole 15 feet	Local Fabricated , Feet 14AWG with Base Stands Including Fixing in Concrete Works ,	Each	5
9	Civil Works	Including Cutting of Concrete bends , Refilling of Sand and Gravel , Plaster after Conduits laying	Meter	496
10	IRM	Conducting , Labels , Drills , Tags , Connectors , Pig Tails , Patch Chords, Cabinets for NVR & POE Switches	Set	1
11	Installation & Commissioning	Including Lodging, Food , Traveling & Services Charges	Job	1

ANNEXURE-A

Terms and Conditions for Tender

1. The quotes should be sent to OGDCL Nashpa Oil & Gas Field, C/O Manager TCS Office Kohat, KPK in closed envelope addressed to Field Manager/ Incharge Telemetry).
2. Bids to be submitted on Single Envelope basis.
3. Evaluation criteria of the bids shall be “full consignment wise”. (Technical & Financial evaluation shall be carried out on the complete scope of supply).
4. The materials to be delivered at Nashpa Oil Field. The delivery charges are in the scope of supplier/ bidder.
5. Any required technical clarification/details regarding the material to be supplied must be cleared before submission of bid. No change in submitted bid will be entertained after bid submission date.
6. The consignment will be accepted after final inspection at site, and payment will be made through Cross Cheque after inspection of material.
7. No advance payment will be made at the time of PO.
8. The firm should have valid NTN and GST number and have active status on FBR website.
9. The Firm should have active Professional tax certificate of concerned Excise office where operating business.
10. Tax submission Certificate (Annex-C) will be provided along with Invoice.
11. The commissioning of CCTV System at site will be the responsibility of supplier.
12. The supplier will provide services free of cost for one year.
13. The materials to be supplied must be in original OEM packaging with standard warranty mentioned in compliance report.
14. Performance bond will also be provided by successful bidder before issuance of P.O
15. OGDCL reserves the right to reject any or all the bids without assigning any reason.
16. Quoted prices must be firm in Pak rupees on for Nashpa Oil & Gas field basis (inclusive of GST, other taxes, and duties).
17. The successful bidder will be responsible to provide all the materials within 45 days after the issuing of P.O date.
18. The delivery and inspection of material will be carried out at Nashpa Oil Field. In case of rejection all the transportation charges will be at Supplier/Bidders end.
19. The material delivery charges to Nashpa Field will be paid by supplier/bidder.
20. Income tax/w. holding tax deductions will be applicable as per company/govt. rules.
21. Compliance report is compulsory along with submission of Bid documents.