

SCHEDULE OF REQUIREMENT

Supply of Emergency Equipments as specified here under:

Items	Requirements/Specifications BRAND & TYPE	Quantity
CO2 (Fire Extinguisher)	CO2 05-KG F/Ext STEEL (CO2-05G-STEEL) KS 5 ST Carbon Dioxide Alloy Steel Fire Extinguisher with Wall Bracket 05-kg capacity, (±10%) DIN EN3, GS, MED, BSI European approved brand	05
DCP (Fire Extinguisher)	DCP 12-Kg F/Ext Stored Pressure (PD12GA) (DCP12G-SP) Dry Chemical Powder Fire Extinguisher 12-kg capacity, C/W wall bracket, pressure gauge and initial charge, DIN EN3, GS, MED, BSI European approved brand	05
Foam (Fire Extinguisher)	Foam AFFF 09-Ltr F/Ext S-9DLWD (AFFF-09G) AFFF (Foam) Fire Extinguisher 09-ltr. Capacity, Model: S9DLWB C/W wall bracket, pressure gauge & initial charge DIN EN3, GS, MED, BSI European approved brand	05
Wind Sock	Wind Sock Local Wind Sock Metal Consists Of Iron/Steel Bars With welded joints front dia 2 ft. Approx. Rear dia 1 ft approx. Bearing is provided Under Inverted Socket Reducer For Friction less 360° movement, fixed on vertical solid 3/4" dia steel bar with b.s. threaded end (for extension) additional inclined bar is provided for anti-deflection	03
Snake Catcher	[RAQ-PSI-SNA-0002] Snake Catcher 40" SS Material (snake-40) Snake Catcher Material SS For any size snake Size: 40" (3.3 feet)	02
Fire Blanket	Blankets Fire 1.8 X 1.8 Fire blanket made of two layers woven Fibre glass fabric with an inner layer of fire retardant film C/W attractive case Size 1.8 x 1.8m	03
Electric Siren- 1 (HP) Local	Electric Siren-1, (1 HP) Local Electric Siren 1-HP, 3000 R.P.M. 220-Volt single phase	01
Full Body Harness	[SKU 70007904686] 1310111 - 3M Harness Protecta 1310111 3M Full Body Harness Protecta First Harness With Chest D-Ring And Work Positioning Belt Attachment: One Chest & Dorsal D-Ring For Rescue & Fall Arrest, Belt For Work Positioning Adaptability: Adjustable Chest And Thigh Strips Ergonomic: Ideally Positioned Sit-Strap For Extended Comfort Material: 44mm Polyamide Web Compliance to EN361 & EN358 Standard "Protecta, by 3M European approved brand	02
Hose Pipe 2-1/2" (100 ft)	Hose Pipe 2 1/2" Dia Red 100FT C/W Original Coupling OSW (Hose-2.5-Uni) Fire Hose, Red Color Extremely resistant to abrasion, heat, seawater, weather, oil & petrol, alkalies, acids, chemicals, ageing ozone and UV rays. 100% high tenacity synthetic yarn, circular woven jacket embedded in a compact vulcanized rubber with high quality special synthetic rubber lining extruded through the weave. Longitudinal ribs in the external covering for high abrasion resistance. Approvals: BS 6391 TYPE 3, PrEN 1924 CLASS 4 & M.E.D. 96 / 98 / EC Working Pressure: 20 bar Bursting Pressure: 60 bar 2-1/2" DIA x 100FT 'OSW' European approved brand Fitted with male / female light Alloy BS – couplings.	02
Jet Nozzle (2" x 12')	Jet Nozzle 2" x 12" Dia, Brass Material	02
Triple Purpose (TP) Nozzle	Tripple Purpose (TP) Nozzle 2-½" dia, (N666P) For Jet, Spray & Fog, Brass Material:.	02
Fire Suit Large	[CHN-PSI-SUI-0001] Fire Suit Aramid Large FF-1080 - Reflective signs (5cm wide) on hem, cuffs, and trousers for visibility - Four-layer fabric for protection and comfort: - Outer layer: 93% Meta-aramid, 5% Para-aramid, 2% Antistatic fabric; flame retardant, washable, low shrinkage - Waterproof and breathable layer: Aramid non-woven fabric with PTFE membrane - Heat insulation layer: Aramid water insulation felt; flame retardant, thermally stable - Comfort layer: Aramid viscose flame retardant material; breathable, anti-static - Three pockets on jacket: two large pockets near hem, one walkie-talkie pocket on left chest Conforms to EN 469 European Approved Brand or USA	01
SCBA	[UK-PSI-SIG-0008] 2003981 - CYL-FWC-2460-BD-PG, 9-Ltr 60-Min 300-Bar Carbon Fibre Cylinders Scott U.K (MAC-6) CE specification, cylinder design life 15 years complete with cylinder valve incorporating safety locking hand wheel 2460 liter free air capacity providing total duration of 61 minutes MAKE : SCOTT ORIGIN : U. K.	01

DCP Trolley	DCP 50-kg S/P Trolley (PD50) (DCP-50GSP) Dry Chemical Powder fire extinguisher Trolley mounted 50-kg capacity (±10%) Stored pressure type European Approved Brand	02
Hose Pipe 2-1/2” (50 ft)	Hose Pipe 2 1/2" Dia Red 50FT C/W Original Coupling OSW (Hose-2.5-Uni) Fire Hose, Red Color Extremely resistant to abrasion, heat, seawater, weather, oil & petrol, alkalies, acids, chemicals, ageing ozone and UV rays. 100% high tenacity synthetic yarn, circular woven jacket embedded in a compact vulcanized rubber with high quality special synthetic rubber lining extruded through the weave. Longitudinal ribs in the external covering for high abrasion resistance. Approvals: BS 6391 TYPE 3, PrEN 1924 CLASS 4 & M.E.D. 96 / 98 / EC Working Pressure: 20 bar Bursting Pressure: 50 bar 2-1/2" DIA x 50FT 'OSW' European Approved Brand Fitted with male / female light alloy BS – couplings.	02

TERMS AND CONDITIONS:

TE/HSE-01/MOF/2024

1. The quotes should be sent in closed envelop along with brochure of the offered model, at the cost of bidder, addressed to:

Field Manager,
Mela Oil Field (OGDCL),
C/o Manager TCS Office Kohat, KHYBER PAKHTUNKHWA.

2. The variation in Quantity will not change the unit cost of material.
3. The quotes will be open on the date as mentioned in the tender notice; the supplier can mobilize his representative to site to participate in the bid opening meeting.
4. Bid bond 02 % of the Bid amount in favor of Field Manager Mela Oil Field is mandatory along the bid submission.
5. Successful bidder will be responsible/Liable to address any complaints arises in their supplied units for a period of six months from the date of delivery.
6. The successful bidder will be responsible to supply all the mentioned items within 02 weeks after the issuing of P.O date.
7. No advance payment will be made at the time of PO.
8. The material delivery charges to Mela Oil Field will be paid by supplier/bidder.
9. The delivery and inspection of material will be carried out at Mela Oil Field (Shakardara). In case of rejection all the transportation charges will also be borne by the Supplier.
10. The payment will be processed after receiving all the fire extinguishers & Trolleys at Mela oil field and submission of Annex-C in FBR by the supplier.
11. All Govt. taxes including GST will be applicable.
12. Payment will be made through cross cheque or through online banking transaction in the supplier's bank account through given IBAN.
13. The OGDCL retain the right to cancel or reject or accept any bid and in the bidding process, reject all the bids without any reason and at any time prior to award purchase order.

Distribution of Emergency Equipments be purchased for Mela #6 Gathering Facility

Sr. #	Distribution Plan	Presently Available	Req. Quantity
1	Mela #6 Gathering Facility	Nil	As per mentioned