



**OIL AND GAS DEVELOPMENT COMPANY LIMITED
NASHPA OIL FIELD & GAS PROCESSING PLANT**

SCHEDULE OF REQUIREMENT

TENDER ENQUIRY # TE-NOF-M-17-2024

S#	Description	Reference #	Rate	Total rate (inclusive of all Taxes)	Deviation
1	As per attached list	Hiring of Services for Painting/ Coating (material with services) of Plant Vessels, Pipes & Structure at Nashpa Oil Field			

Sr No.	Description	Unit Rate	Paint Area
1.	<p>Services for Epoxy and PU Painting/ Coating of Plant Vessels, Pipes & Structure at Nashpa Oil Field</p> <p><u>Vessels:</u> First Coat: Inorganic zinc silicate (40-50 Micron DFT) Second Coat: Inorganic zinc silicate (40-50 Micron DFT) Third Coat: Alkyd Enamel (20-25 Micron DFT) Fourth Coat: Alkyd Enamel (20-25 Micron DFT) Total Minimum Thickness: 120-150 Micron</p> <p><u>Piping:</u> Primer Coat: Inorganic zinc silicate primer (50-55 Micron DFT) Inter Coat: Heat Resisting paint, Silicone Resin (25 Micron DFT) Finish Coat: Heat Resisting paint, Silicone Resin (25 Micron DFT) Total Minimum Thickness: 100-105 Microns</p>	Sq.ft	17000 Sq.ft

TERMS AND CONDITIONS:

1. Service Team along with material shall be mobilized within 04 weeks from the date of issuance of purchase order and project completion time is 08 weeks.
2. Enamel (Top Coat) will be Light Grey color (RAL-7035)
3. Surface preparation shall be as per SSCP-SP-2 standard (Sand paper, Sand block, wire brush and paint remover).
4. Scaffolding will be contractor responsibility.
5. Supervising engineer at least have SSPC level 2/ NACE certification and he/she must be a regular employee of the company.
6. Compatibility of surface must be tested. Contents will be mixed well before application. Surface must be made dust free prior to applying any coat. Storage must be done according to MSDS, product must not contain heavy metals.
7. Only paint manufacturing company can apply for this project.
8. Bidder to provide unit rate, OGDCL reserve the right to change the scope in Purchase Order. Evaluation will be made on the complete scope of work.
9. OGDCL reserves the right to cancel the tender at any stage before placement of firm Purchase Order.
10. Original Bid bond must be submitted along with the bid.

11. Any required clarification/ detail regarding ordered material must be cleared before submission of bid. No change in submitted bid will be entertained after bid submission date.
12. Acceptance will be decided after comprehensive final inspection and payment will be made through Cross Cheque.
13. Contractor must have 3 years plus experience in Oil & Gas sector. List of relevant POs and company profile to be attached along with the bid.
14. Firm should have valid NTN and GST number and have active status on FBR website.
15. Tax submission Certificate (Annex-C) will be provided along with Invoice.
16. Tax Exemption certificate (if any) has to be submitted with the invoice.