

SCHEDULE OF REQUIREMENT

Description and Quantity Requirements:

Field	Sr. #	Qty	Location/Description
Nashpa Oil & Gas Field	01	14 Nos.	At 07 NOF well sites.
	02	01 No.	At NOF CCR

As per following specifications:-

1. Earthing/Grounding for towers and Equipments including the manhole for earthing maintenance. Desired value less than 1 ohms.
2. Bore type, earthing up to permanent water level/moist soil by arrangement of earth pit/point comprising of concrete/brick work housing with lifting cover 2 inch dia, perforated GI pipe, appropriate bare copper conductor 10ft , 20 mmsq dia. (**minimum 30ft bore or bore depth up to underground water level, whichever is higher will be applicable**).
3. The earthing and bonding shall be completed with fixing clamps etc. & all metal works shall be bonded to the proposed earthing network.
4. Supply and installation of 2 Nos. 10 mm² bare stranded electrolytic copper conductor lead in pre-laid G.I pipe and connected to tinned copper spike. 02 Nos. leads to be installed including all accessories like brass nuts, bolts, washers etc. complete in all respect.
5. Chemical - local and Klomite, Earthing powder, Lime stone, sand, gravel, cement, etc as per requirement. All the material will be inspected at site.
6. Tinned earth test link in earthing pit consisting of copper rod (12"x2"x1/2") with fixing arrangement on the wall of man hole including brass nuts, bolts washers lugs etc. complete in all respect.
7. Construction of earth pit (manhole) of internal size 18"x18"x 24" deep with 9" thick brick wall with cement mortar, internal plaster 1:4, Metal cover 10mm palate thick cover with lifting hooks including all accessories complete in all respect.
8. Testing and commissioning of the earthing system along with all testing accessories complete in all respect with test/completion certificate. Test equipment certificate will be required during on spot earthing test.

Terms & Conditions

1. The quotes should be sent to OGDCL Nashpa Oil & Gas Field, C/O Manager TCS Office Kohat, KPK in closed envelope addressed to **Field Manager/ Incharge (Telemetry)**.
2. OGDCL reserves the right to reject any or all the bids without assigning any reason.
3. Quoted prices must be firm in Pak rupees on FOR basis (inclusive of GST, other taxes, and duties).
4. The variation in Quantity will not change the unit cost of material.
5. The quotes will be opened on the date as mentioned in the tender notice; the supplier can mobilize his representative to site
6. Bid bond (Bank Draft/Pay Order) of **Rs 2% of the quoted total amount/-** in favor of Field Manager Nashpa Oil & Gas Field at the time of bid submission by all participants.
7. The successful bidder will be bounded to provide the material as per specifications mentioned in the TOR.
8. The successful bidder will be responsible to provide all the materials within 45 days after the issuance of P.O.
9. No advance payment will be made at the time of P.O.
10. The delivery and inspection of material will be carried out at Nashpa Oil Field. In case of rejection, all the transportation charges will be at Supplier's end.
11. The material delivery charges to Nashpa Field will be paid by the Supplier.
12. Income tax/w. holding tax deductions will be applicable as per company/govt. rules.
13. The payment will be made through cross Cheque after receiving the mentioned material at site.
14. The firm should have valid NTN and GST number and have active status on FBR website.
15. The Firm should have active Professional tax certificate of concerned Excise office where operating business.
16. Tax submission Certificate (Annex-C) will be provided along with Invoice.