



Offered Service (s) shall mandatorily comply with following requirements.

Description and Quantity Requirements:

Location	Qty	Description	Requirement
Regional Office Hyderabad.	01 No.	Installation of Filter Plant along with construction of Room '12'15' Ft. At University of Sindh Jamshoro.	<p>1. Construction of 12'15 Room .</p> <p>(1) Construction of Room 12'15 ' from outside of wall and total height from ground level 12" which includes 1' above from ground level and roof height from floor level is 11'</p> <p>(2) Includes RCC Roof , bricks masonry work having wall thickness of 9" , both side plaster ¾" 1:4 ration with iron Door of sizes 4x7"</p> <p>(3) Electric work includes 2 LED Bulbs and 01 Brackets fan size (size 24") includes total four points.</p> <p>(4) 01 underground water Tank of size 5'x5x5' construction with Base and Roof with RCC. 1:2:4 and wall construction with brick masonry of size 9" cover with inside plaster of '1" thickness mixed with pudlo powder and of 1:4 cement.</p> <p>2. Supply & Installation of filter plant.</p> <p>1. Sand filtration system 5000gpd</p> <p>2. Sand filter multimedia "24x 72"</p> <p>3. 03 way valves for sad filter multi media</p> <p>4. Carbon filter multimedia 24x72</p> <p>5. Media for multi media</p> <p>6. Carbon for multi media</p> <p>7. UV panel mount (SS Sump)</p> <p>8. Feed Pump</p> <p>9. PVC piping and valves</p> <p>Note: Filtration plant accessories must be of USA/UK.</p>



Administrative Officer
OGDCL R.O., Hyderabad



31/12/2019
Regional Co-ordinator
OGDCL, R.O, Hyd.