



**OIL AND GAS DEVELOPMENT COMPANY LIMITED
NASHPA OIL & GAS FIELD**

SCHEDULE OF REQUIREMENT

TENDER ENQUIRY # TE/SHEIKHAN (TOGH)/002/19

Welding and Fabrication of Piping of equipment, supports of Cable Trays & Distribution Boxes of Dehydration Unit at Sheikhan Field

S#	Description of Services	Reference #	Rate	Total rate (inclusive of all Taxes)	Deviation
1	As per attached Scope of Work				

SCOPE OF WORK:

S#	Job	Scope	Unit rate	Total
1	Welding / fabrication	2,500 dia inch	(per dia inch)	
2	Painting job	1000 sq feet	(per sq feet)	

1. Welding & Fabrication of Interconnecting pipe spools of all plant equipment. Welding material (electrodes, cutting / grinding discs), grinders & diesel engine welding machines are in contractor's scope.
2. Welding & Fabrication of Pipe supports where required, are inclusive.
3. Painting of all the newly fabricated spools including piping, supports and any other electrical instrument related fabrication. Paint shall be provided by OGDCL.
4. Painting job shall comprise of:
 - a. Thorough cleaning of surface before starting painting job
 - b. 01 coat of Red Oxide
 - c. 02 coats of industrial grade epoxy paint
5. Welding of Electrical & Instrumentation cable trays and fabrication of supports of distribution boards etc.

Note: Dehydration Unit contains Inlet Gas Cooler, Inlet Gas Separator Skid, Re-boiler Skid, Pumping skid, Filter Skid, Flare stack and associated piping.

TERMS AND CONDITIONS

1. OGDCL will not provide any kind of boarding / lodging.
2. Logistics support (Crane, Lifter and Trailer) will be provided by OGDCL.
3. Contractor will provide all kind of PPE's to its labor.
4. All Kind of Equipment, Tool & Consumables (Welding Electrodes, Cutting/Grinding discs, paint-brushes, trays etc.) will be in Contractor's scope.
5. Radiography of the weld joints is in OGDCL's scope. In case of any re-work, no additional payment shall be made.
6. Sand blasting and Hydrotesting with water will be in contractor's scope. Hydrotest pump shall be provided by OGDCL.
7. Pressure testing with N2 will be in contractor scope. N2 gas and pumper will be provided by OGDCL.
8. All kind of utilities Electricity, Water etc. is in Contractor's scope.
9. Bidder must provide prior experience certificates of plant erection and commissioning along with bid documents. Bids without documentation related to experience of plant erection / commissioning / refurbishment will be rejected.
10. After issuance of formal work order, Contractor is to provide services at a schedule given by OGDCL.

11. Payment will be made through Cross Cheque after inspection of completed jobs as per SOR.
12. The Quantities contained in the scope of work for each activity are estimated and liable to change (increase, decrease or omitted) when the work is actually executed. The payment to be made to the Contractor shall be based on the actual quantity of work performed.
13. OGDCL reserves the right to inspect, stop and advise rework for any job either during execution or after execution, if deemed necessary by the Company's representative based on quality of the job, finish of the job or if the job is not being or have been performed in line with the best engineering practices. In this regard the rework will be in Contractor's Scope.
14. Contractor must provide prior experience certificates of its Supervisors, Welders & Fabricators.
15. Contractor is to abide by all safety Rules and Regulations of OGDCL.
16. Partial Payments will not be made, in any case.
17. All participants should carefully read TOR's attached with the Tender documents before submission of Bid.
18. Management of the plant reserves the right to curtail the job list or terminate the services of any hired staff at any time without any reason.
19. Contractor should ensure the police verification of all manpower direct and indirect and must have bio-data file of each.