

Offered Service (s) shall mandatorily comply with following requirements.

Description and Quantity Requirements:

Location	Qty	Description	Requirement
Regional Office Hyderabad.	01 No.	Installation of Filter Plant along with construction of Room '12'15' Ft. At University of Sindh Jamshoro.	<p>1. Construction of 12'15 Room .</p> <p>(1) Construction of Room 12'15 ' from outside of wall and total height from ground level 12" which includes 1' above from ground level and roof height from floor level is 11'</p> <p>(2) Includes RCC Roof , bricks masonry work having wall thickness of 9" , both side plaster ¾" 1:4 ration with iron Door of sizes 4x7"</p> <p>(3) Electric work includes 2 LED Bulbs and 01 Brackets fan size (size 24") includes total four points.</p> <p>(4) 01 underground water Tank of size 5'x5x5' construction with Base and Roof with RCC. 1:2:4 and wall construction with brick masonry of size 9" cover with inside plaster of '1" thickness mixed with pudlo powder and of 1:4 cement.</p> <p>2. Supply & Installation of filter plant.</p> <ol style="list-style-type: none"> 1. Sand filtration system 5000gpd 2. Sand filter multimedia "24x 72" 3. 03 way valves for sad filter multi media 4. Carbon filter multimedia 24x72 5. Media for multi media 6. Carbon for multi media 7. UV panel mount (SS Sump) 8. Feed Pump 9. PVC piping and valves <p>Note: Filtration plant accessories must be of USA/UK.</p>

Administrative Officer
OGDCL R.O., Hyderabad

Regional Co-ordinator
OGDCL, R.O., Hyd.

31/12/2019