


Offered Service (s) shall mandatorily comply with following requirements.

**Description and Quantity Requirements:**

Location	Qty	Description	Requirement
Regional Office Hyderabad.	01 No.	Installation of Filter Plant along with construction of Room '12'15' Ft. At University of Sindh Jamshoro.	<p><b>1. Construction of 12'15 Room .</b></p> <p>(1) Construction of Room 12'15 ' from outside of wall and total height from ground level 12" which includes 1' above from ground level and roof height from floor level is 11'</p> <p>(2) Includes RCC Roof , bricks masonry work having wall thickness of 9" , both side plaster ¾" 1:4 ration with iron Door of sizes 4x7"</p> <p>(3) Electric work includes 2 LED Bulbs and 01 Brackets fan size (size 24") includes total four points.</p> <p>(4) 01 underground water Tank of size 5'x5x5' construction with Base and Roof with RCC. 1:2:4 and wall construction with brick masonry of size 9" cover with inside plaster of '1" thickness mixed with pudlo powder and of 1:4 cement.</p> <p><b>2. Supply &amp; Installation of filter plant.</b></p> <ol style="list-style-type: none"> <li>1. Sand filtration system 5000gpd</li> <li>2. Sand filter multimedia "24x 72"</li> <li>3. 03 way valves for sad filter multi media</li> <li>4. Carbon filter multimedia 24x72</li> <li>5. Media for multi media</li> <li>6. Carbon for multi media</li> <li>7. UV panel mount (SS Sump)</li> <li>8. Feed Pump</li> <li>9. PVC piping and valves</li> </ol> <p>Note: Filtration plant accessories must be of USA/UK.</p>



Administrative Officer  
OGDCL R.O, Hyderabad



31/12/2019  
Regional Co-ordinator  
OGDCL, R.O, Hyd.