

OIL & GAS DEVELOPMENT COMPANY LIMITED

Mela Oil FIELD

SCHEDULE OF REQUIREMENT

Tender Enquiry No: TE/MOF/ELECT/10017979/2024

“Supply of Main LT MCC Panel for Mela 6 Surface Facility”

S. NO.	DESCRIPTION / Part No.	UNIT	QTY.	Unit price (PKR)	Total price (PKR) inclusive of GST	Delivery /Completion Period Offered	Deviation from tender Spec. if any
1	Panel Board 14SWG SIZE (1500(2*700)450mm Indoor/Floor Mounted	Nos.	1			06 WEEKS	
	INCOMING						
1	MCCB 400A 4P 50KA, Schneider/ABB/Terasaki or Equivalent	Nos.	2				
2	Mechanical Interlocking	Nos.	1				
3	Digital Volt Meter (0-500V)	Nos.	2				
4	Volt Selector Switch	Nos.	2				
5	Digital Amp Meter (400/5A)	Nos.	2				
6	Amp Selector Switch	Nos.	2				
7	CT 400/5A	Nos.	6				
8	Pilot Lights (R/Y/B)	Nos.	6				
9	Control Fuse with Base 2A (R/Y/B)	Nos.	6				
	OUT GOING						
1	MCCB 15A 3P 15KA Schneider/ABB/Terasaki or Equivalent	Nos.	1				
2	MCCB 30A 3P 15KA Schneider/ABB/Terasaki or Equivalent	Nos.	4				
3	MCCB 50A 3P 15KA Schneider/ABB/Terasaki or Equivalent	Nos.	1				
4	MCCB 60A 3P 15KA Schneider/ABB/Terasaki or Equivalent	Nos.	1				
	ASD STARTER 7.5KW	Nos.	2				
1	MCCB 15A 3P 15KA Schneider/ABB/Terasaki or Equivalent	Nos.	2				
2	Magnetic Contactor 3P (LC1-D18) Schneider/ABB/Terasaki or Equivalent	Nos.	4				
3	Magnetic Contactor 3P (LC1-D09) Schneider/ABB/Terasaki or Equivalent	Nos.	2				
4	Thermal Over Load (7.0-10A) Schneider/ABB/Terasaki or Equivalent	Nos.	2				
5	Timer Autonics/Hyundai or Equivalent	Nos.	2				
6	H-O-A Switch TP	Nos.	2				
7	Push Buttons (ON/OFF) Best Quality	Nos.	4				
8	Indication Lights (ON/OFF/Trip Indication)	Nos.	6				
9	Control Fuse 2A With base	Nos.	4				
10	Control Terminal Block 2.5mm	Nos.	12				

S. NO.	DESCRIPTION / Part No.	UNIT	QTY.	Unit price (PKR)	Total price (PKR) inclusive of GST	Delivery /Completion Period Offered	Deviation from tender Spec. if any
11	Power Terminal Block 6mm	Nos.	6				
12	Tube Light	Nos.	2				
13	Limit Switch	Nos.	2				
14	Louver with mash	Nos.	4				
15	Exhaust Fan 6"/8"	Nos.	2				
16	Thermostate Switch	Nos.	1				
17	Bus Bar & Insulator	Set	1				

Note:

1. The Supplier shall be bound to replacements of defective equipment / components (If any), at his own cost including transportation..
2. Required Complete supplies as per SOR.
3. Supplier will provide complete BOQ, and supply will be delivered at site i.e.Chanda Field.
4. Interested parties may site visit i.e. Mela-06 Well prior approval by competent authority as per SOP before making any proposal for scope of requirement.