



**OIL AND GAS DEVELOPMENT COMPANY LIMITED
NASHPA OIL & GAS FIELD**

SCHEDULE OF REQUIREMENT

TENDER ENQUIRY # TE/NOF/M/12/2022

The bid to be submitted as per below format:

Item no	Description	Reference #	Rate per unit		Total rate (inclusive of all Taxes)	Deviation
1	As per attached list (following pages)					

Detail of Coating/Painting			
Sr No.	Description	Unit	Qty
1.	FINAL COAT: Polyurethane Enamel, ICI Berger or Equivalent. COLOR: Silver TEMP: -20°C<operating temperature≤90°C 40-50 microns DFT	Litres	200
2.	FINAL COAT: Polyurethane Enamel, ICI Berger or Equivalent. COLOR: Light Grey (RAL No. 7035) TEMP: -20°C<operating temperature≤90°C 40-50 microns DFT	Litres	280
3.	FINAL COAT: Polyurethane Enamel, ICI Berger or Equivalent. COLOR: Silver Grey (RAL No. 7001) TEMP: -20°C<operating temperature≤90°C 40-50 microns DFT	Litres	225
4.	FINAL COAT: Polyurethane Enamel, ICI Berger or Equivalent. COLOR: Yellow (RAL No. 1018) TEMP: -20°C<operating temperature≤90°C 40-50 microns DFT	Litres	48
5.	PRIMER COAT: Inorganic Zinc Silicate Primer, ICI Berger or Equivalent. COLOR: for Silver Metallic final coat TEMP: 90°C<operating temperature≤400°C 50-55 microns DFT	Litres	150
6.	INTERMEDIATE COAT: Heat Resisting Paint (Silicone Resin), ICI Berger or Equivalent. COLOR: for Silver Metallic final coat TEMP: 90°C<operating temperature≤400°C 25 microns DFT	Litres	76
7.	FINAL COAT: Heat Resisting Paint (Silicone Resin), ICI Berger or Equivalent. COLOR: Silver Metallic TEMP: 90°C<operating temperature≤400°C 25 microns DFT	Litres	76
8.	FINAL COAT: Heat Resisting Paint (Silicone Resin), ICI Berger or Equivalent. COLOR: Silver Grey (RAL No. 7001) TEMP: 90°C<operating temperature≤400°C 25 microns DFT	Litres	148
9.	THINNER (for Polyurethane Enamel paint)	Litres	160
10.	THINNER (for In-organic Zinc Silicate paint)	Litres	60
11.	THINNER (for Silicone Resin paint)	Litres	40

TERMS AND CONDITIONS:

1. Bidding procedure: single envelope
2. Evaluation criteria: Complete consignment wise (all items have to be quoted otherwise the bid will be rejected).
3. If the exact quantity in litres cannot be supplied by the bidder, then the items in near equivalent quantities as per standard size of the packaging of paints / thinners can be quoted. The evaluation shall be done as per unit rate of each item.
4. Delivery period for ordered material will be minimum 03 weeks from the date of issuance of purchase order.
5. Date of Manufacturing shall not be older than 10 weeks.
6. The offered material must be industrial grade quality, evidence to be provided along with bid documents.
7. The Ordered material will be delivered at Nashpa Oil Field. The delivery charges to Nashpa Oil Field to be borne by the supplier/ bidder.
8. The shipment shall be delivered in single complete package.
9. Technical & Financial evaluation will be made on the complete scope of supply.
10. Any required clarification/details regarding ordered material to be supplied must be cleared before submission of bid. No change in submitted bid will be entertained after bid submission date.
11. The consignment will be accepted after final inspection at site, and payment will be made through Cross Cheque.
12. The bidder should offer a brand have minimum 10 years of manufacturing experience for supply of industrial paints to chemical, cement, fertilizer or oil and gas companies within Pakistan.
13. The firm should have valid NTN and GST number and have active status on FBR website.
14. The Firm should have active Professional tax certificate of concerned Excise office where operating the business.
15. Tax submission Certificate (Annex-C) will be provided along with Invoice.