



**OIL AND GAS DEVELOPMENT COMPANY LIMITED
NASHPA OIL & GAS FIELD**

Date: 26-07-2022

SCHEDULE OF REQUIREMENT

TENDER ENQUIRY # TE/WALI/001/2022

Hiring of Technical Services for Loading, Unloading & Installation of Dehydration Unit & Membrane Unit for Wali Development Project

S#	Description of Services	Reference #	Rate	Total rate (inclusive of all Taxes)	Deviation
1	As per attached Scope of Work				

SCOPE OF WORK:

1. Loading of enlisted skids & vessels of Separation Unit, Membrane Unit and Dehydration Unit on cargo trailers for shifting at Nashpa Plant, Karak.
2. Un-loading of enlisted skids & vessels of Separation Unit, Membrane Unit and Dehydration Unit from cargo trailers after shifting at Wali Project Site
3. Installation & erection of enlisted skids & vessels of Separation Unit, Membrane Unit and Dehydration Unit at designated foundations at Wali Project Site.
4. Execution of Leak test after Installation of unit.

S.No	Description	Activity Cost in PKR
SEPARATION AREA SKIDS		
1	ECONOMIZER HEAT EXCHANGER	
2	WATER BATH HEATER-A	
3	FUEL GAS SKID	
MEMBRANE UNIT SKIDS		
4	INLET K.O. VESSEL	
5	COALESCER FILTER SKID	
6	WATER BATH HEATER-B	
7	CHARCOAL FILTER SKID	
8	PARTICLE/CARTIRIDGE FILTER SKID	
9	MEMBRANE SKID	
DEHYDRATION UNIT-A		
10	FEED GAS COOLER	
11	INLET GAS SEPARATOR SKID	
12	GLYCOL CONTACTOR TOWER	
13	OUTLET SEPARATOR	
14	GLYCOL REGENERATOR SKID	
15	GLYCOL SUMP TANK	
16	FLARE K.O. DRUM	
17	FLARE STACK	
Total		
Taxes (GST, PST etc)		
Grand Total		

TERMS AND CONDITIONS

1. All bidders are advised to visit Nashpa Site in order to correctly assess scope of work
2. Bidders will provide previous experience of erection and installation of Gas Processing Plant. Bidder must have a minimum of 10 years' relevant experience.
3. OGDCL will provide suitable area to contractor for setting up lodging facility.
4. Logistics support (Crane, Lifter and Trailer) will be provided by OGDCL.
5. Contractor will provide all kind of PPE's to its labor.
6. Certified Riggers with valid, current & traceable certificates from a reputable firm are mandatory for the execution of job. In case certificates are not acceptable to OGDCL for any reason, Contractor is bound to replace the personnel without any delay
7. All kind of Equipment, Tools & Consumables will be in contractor's scope.
8. Valid Third Party Certification of Lifting equipment from a reputable firm will be accepted only. Certificates shall be traceable and in case of non-compliance Contractor will be bound to replace the same without any delay.
9. OGDCL will provide utilities like Electricity & Water for job execution only.
10. After issuance of formal work order, Contractor is to provide services as per schedule provided by OGDCL.
11. Payment will be made through Cross Cheque after inspection of completed jobs as per SOR.
12. Determination of safe Shifting strategy for all equipment is in Contractor's Scope. However, Contractor will be required to submit rigging study in hard form before loading/unloading of any equipment, and the same is bound to be pre-approved from OGDCL representative.
13. Contractor is bound to submit rigging study and give OGDCL adequate time to arrange Logistics accordingly.
14. If during execution of work, some minor on-skid dismantling work is required in order to ensure safe loading/ unloading, this will be in Contractor's scope
15. Contractor is to abide by all safety Rules and Regulations of OGDCL.
16. Partial Payments will not be made, in any case. Payment will be made after successful completion of the project and submission of Annexure 'C'. Bidder must be registered with FBR and having active tax payer status.
17. Bidders should carefully read TOR's before submission of Bid.
18. Management of the plant reserves the right to curtail the job list or terminate the services of any hired staff at any time without any reason.
19. Contractor should ensure the police verification of all manpower direct and indirect and must have bio-data file of each.
20. Contractor to follow OGDCL HSEQ procedures