

Oil and Gas Development Company Limited
Corporate Social Responsibility Department
SPECIFICATIONS OF TENTS

1	Description	Family tent of double fly single fold, having standard size 4 x 4 meters, with ground sheet of PE material
2	Material	Outer fold of heavy water proof, rot proof cotton cotton canvas, weight 420 – 450 gsm (+_5%). Inner fold of heavy water proof, rot proof cotton canvas weight 420-450gsm (+_ 5%)
3	Size and measurement	<ul style="list-style-type: none"> a. Size 4x4 meters b. Minimum Rigid length – 4 meters c. Minimum central height – 2 meters d. Minimum side wall – 0.9 meters e. Windows on both side – 2 x 2 fts f. P.E Ground sheet (150gsm) – 4 x 4 meters g. PE Mud flap (150 gsm) – 10 inches must h. Size of outer flap – 12 inches must i. Front Hood – Canvas or PE material j. Colour – off white or white however other colors will also be considered. k. Weight – 40-50 kgs l. Instruction page for pitching
4	Accessories of Tent	<ul style="list-style-type: none"> a. Two standing iron poles of M.S. Pipe of 1.5 inch of 15SWG with base. b. One rigid iron pole in two pieces of equal size joined together with a 10 inch long socket of larger dia welded to one piece. Welding should be complete and touching welding will not be accepted. c. 8 x good quality ropes of 3 meters on each side and 02 x ropes of 4 meter on front / back side of tent. The rope cotton undyed with reinforcement of cloth pads along with 12 runners (one with each rope). Branded rope shall also be accepted. d. 1 x hammer with wood or plastics handle of approx. 1 kg e. 10 x pegs of large size for outer pitching (MS bar 5/8"x14") f. 16 x pins for mud flap pitching (MS bar 3/8"x8") g. 3 x packing bags, one each for the tent canvas, tents poles and accessories.
5	OGDCL Color Logo	<ul style="list-style-type: none"> a. OGDCL Color Monogram of 2 x 2 feet dia on both side of the tent to be printed / pasted at central fly of the tent. (outer fly) b. Small Monogram of OGDCL 1'x1' feet dia to be printed / pasted at center of the tent bag / cover.
6	Special Instructions	Manufacture Name and NOT FOR SALE on inner / outer cover should be printed

Oil and Gas Development Company Limited
Corporate Social Responsibility Department

1. All the tents will have OGDCL Logo imprinted or screened on them per following sample: -



2. Sample of 1 Meter of the cloth being used for tent to be provided with the bid.
3. 1500 Nos of tents will be procured.
4. Evaluation Criteria will be Full Consignment Wise.
5. Delivery Terms will be Part Delivery Part Payment.
6. Bid Bond of Rs. 200,000/- in form of Pay order in Favor of OGDCL to be submitted with the bid.
7. The prospective bidder should have valid NTN and STRN
8. Bidders with ready stock will be preferred however 04 days period will be provided for delivery from issuance of formal LPO.
9. The quoted prices will be Ex Works.