



**OIL AND GAS DEVELOPMENT COMPANY LIMITED**  
**TOGH GAS FIELD**

Date: 05-03-2021

**SCHEDULE OF REQUIREMENT**

**TENDER ENQUIRY # TE/TOGH/PROD/01/2021**

Procurement of Material required for Construction of Test Header at Togh Well

S#	Description	Reference #	Rate	Total rate (inclusive of all Taxes)	Deviation
1	As per attached list				

### Detail of Material with Specs

S. No	Description	Qty
1	Ball Valve 4", 900 #, A216 WCB Flange RTJ Ball SS Seat RPTFE	4
2	Flange 8", 900 #, WN, RTJ, Sch-80 A105	6
3	Flange 4", 900 #, WN, RTJ, Sch-80 A105	14
4	Blind Flange 8", 900 # RTJ A105	2
5	Blind Flange 4", 900 # RTJ A105	2
6	Eq. Tee 8", Sch-80 BW A234 WPB	2
7	Reducing Tee 8"x4", Sch-80 BW A234 WPB	3
8	Elbow 8", Sch-80, 90° BW A234 WPB	4
9	Elbow 4", Sch-80, 90° BW A234 WPB	10
10	Elbow 4", Sch-80, 45° BW A234 WPB	8
11	Conc. Reducer 8"x4", Sch-80 BW A234 WPB	1
12	Conc. Reducer 8"x6", Sch-80 BW A234 WPB	1
13	Conc. Reducer 6"x4", Sch-80 BW A234 WPB	1
14	R-49 Ring joint Gasket SS 316	10
15	R-37 Ring joint Gasket SS 316	15
16	Stud Bolts with two Nuts M 1 <sup>3</sup> / <sub>8</sub> " x 230 A 193 B7 / A 194 2H GALV	100
17	Stud Bolts with two Nuts M 1 <sup>1</sup> / <sub>8</sub> " x 175 A 193 B7 / A 194 2H GALV	160

**TERMS AND CONDITIONS:**

1. The material will be delivered at Togh Gasl Field. The delivery charges to Togh Gasl Field to be borne by the supplier/ bidder.
2. MTC of the material along with valid heat number must be provided.
3. Any required technical clarification/detail regarding material to be supplied must be cleared before submission of bid. No change in submitted bid will be entertained after bid submission date.
4. European/US/Canadian origin valves & flanges must be quoted.
5. Gaskets of Flexitallic or equivalent brand must be quoted
6. Technical & Financial evaluation will be made on the complete scope of supply.
7. The material must be supplied within 02 weeks from the date of PO placement.
8. Certificate of Origin to be provided by vendor at the time of delivery.
9. Material will be accepted after final inspection at site, and payment will be made through Cross cheque thereof.
10. The firm should have valid NTN and GST number and have active status on FBR website.
11. The Firm should have active Professional tax certificate of concerned Excise office where operating business and same to be submitted along with the bid.
12. Tax submission Certificate (Annex-C, submitted status) should be provided along with Invoice.
13. BOE, GD or SRO to be submitted along with invoice for Income tax/GST exemption if any.
14. The supplier should have 10 years of prior experience of supply of piping material.