



**OIL AND GAS DEVELOPMENT COMPANY LIMITED  
MELA OIL FIELD**

Date: 09-10-2020

**SCHEDULE OF REQUIREMENT**

**TENDER ENQUIRY # TE/MOF/PE&FD/005/2020**

Services Required for Internal Sand Blasting and Epoxy Coating of 02 Nos. 8000 Barrels Crude Oil Storage Tank-05 and Tank-06 at Mela Plant.

<b>S#</b>	<b>Description</b>	<b>Reference #</b>	<b>Rate</b>	<b>Total rate (inclusive of all Taxes)</b>	<b>Deviation</b>
1	As per attached list				

### **SCOPE OF WORK:**

Job includes internal Sand blasting and Epoxy Coating/Painting of complete internal surfaces of 02 Nos. Crude Oil Storage Tanks at Mela plant. Below given is the detailed scope of work including but not limited to;

- Sand Blasting of Tanks as per SA 1.5-2.5 standard.
- Supply of Sand.
- Supply of Compressor.
- Supply of Diesel & all other accessories/equipment required to carry Sand Blasting job.
- Primer/Base coat: Single coat of Berger Epilux 78 Zinc Phosphate Primer or any equivalent product having DFT of at-least 100 microns.
- Finish coat: Two coats of Berger Epilux 300 Polyimide Cured High Build Epoxy or any equivalent product having DFT of at-least 150 microns.
- Supply of Epoxy, Primer, Thinner & Hardener.
- All other accessories/equipment required to carry Epoxy Coating job.
- Capacity of Both Storage Tanks is 8000 Barrels each having 13.716 Meters Diameter and 9.01 Meters Height.
- OGDCL will provide Electricity only for lights.

### **TERMS AND CONDITIONS:**

- **Bids are required in PKR against mentioned scope of work. Detail of jobs (scope of work) is elaborated in tender documents.**
- HSEQ Rules & Regulations will be strictly observed.
- Mela Plant is active location and extreme safety measures are required during execution of job as surrounding Crude Oil Storage Tanks are in service.
- Use of mobile phone and camera is prohibited in the plant premises.
- Delivery period of services will be 6-8 weeks from the date of issuance of work Order, and should be completed within agreed time frame.

- Services will be delivered at Mela Oil Field Shakardara, District Kohat.
- Any required technical clarification/details regarding services mentioned above must be cleared before submission of bid. No change in substance of bid will be entertained after bid submission date.
- Completion of job will be accepted after final inspection at site, and payment will be made through Cross Cheque thereof.
- Firm should have relevant work experience and share Clients PO/work completion certificates with Technical Bid.
- Skilled manpower should be well experienced in their respective crafts.
- The firm should have valid NTN, GST and KPRA registration having active status.
- The Firm should have active Professional tax certificate of concerned Excise office where operating business.
- FBR and KPRA Annex-C in submitted status to be provided at time of payment.
- BOE, GD or SRO to be submitted along with invoice for Income tax/GST exemption if any.

**CONTRACTOR'S RESPONSIBILITIES:**

- Site administration personnel with associated resources.
- Provision of PPE (Safety helmet, Coverall, safety shoes, gloves etc.) to all crew.
- All kind of tools required for the job.
- Scaffolding material & services as per requirement.
- Meals, refreshment to all the Crew, OGDCL will only provide accommodation upto 08 persons.
- Pick and drop from Plant to accommodation and back.
- In case of any accident, medical treatment or compensation, whichever is applicable.
- Electrical Supply Boards along with cables as per HSE standard.
- Proper housekeeping of area where job being executed and after completion.