

**TENDER NOTICE FOR THE CONSTRUCTION OF BOUNDARY WALL AT GOVT. PRIMARY SCHOOL,
VILLAGE MUHAMMAD YOUSAF CHACHAR UC QADIRPUR TEHSIL & DISTT. GHOTKI.**

BILL OF QUANTITY

Sr.#	Description	Quantity	Unit	Rate per Rft (Rs)	Total Amount (Rs).
1	Construction of boundary wall(as per X-Section attached) or instruction of Engineer in charge including <ol style="list-style-type: none"> 1. Excavation in foundation upto 2.5’. 2. PCC 1:4:8 in foundation (6” thick). 3. Brick masonry in 1:4 cement mortar in foundation & super structure. 4. DPC (50mm thick P.C.C 1:2:4, using 3mm aggregate & finished smooth with steel float, covered with two coats, each of hot bitumen 0.75 kg per Sqm and blinded with 0.012 cum of sand per Sqm. 5. Back Filling 6. RCC 1:2:4 in Columns including Shuttering, steel cutting/binding. 7. Cement Plaster on both sides (inner & outer face) of wall. 8. Fixing of angle post of 4.5’ grouted 1’.00” in Column concrete ,fixing of 12 gauge barbed wire galvd, 2 strands 4 points barbs. 9. Paint work (Emulsion on steel work and weather shield on wall both side). 10. Clearance & cleaning of site after the completion of work. 11. Supply and fixing of steel gate. 	500.00	Rft		
				Total	

TENDER NOTICE FOR THE CONSTRUCTION OF BOUNDARY WALL AT GOVT. PRIMARY SCHOOL,**VILLAGE MUHAMMAD YOUSAF CHACHAR UC QADIRPUR TEHSIL & DISTT. GHOTKI.**

Oil & Gas Development Company Limited is the largest Exploration & Production listed company of Pakistan. The detail about the company can be obtained from website <http://www.ogdcl.com>. Sealed Bid(s) / Quotation(s) are invited from well reputed Firms for the supply of drinking water given below under competitive bidding procedure, as per Public Procurement Regulatory Authority (PPRA) rules.

BILL OF QUANTITY

Sr.#	Description	Quantity	Unit	Rate per foot	Total Amount (Rs).
1	Construction of boundary wall(as per X-Section attached) or instruction of Engineer in charge including 1. Excavation in foundation upto 2..5'. 2. PCC 1:4:8 in foundation (6" thick). 3. Brick masonry in 1:4 cement mortar in foundation & super structure. 4. DPC (50mm thick P.C.C 1:2:4, using 3mm aggregate & finished smooth with steel float, covered with two coats, each of hot bitumen 0.75 kg per Sqm and blinded with 0.012 cum of sand per Sqm. 5. Back Filling 6. RCC 1:2:4 in Columns including Shuttering, steel cutting/binding. 7. Cement Plaster on both sides (inner & outer face) of wall. 8. Fixing of angle post of 4.5' grouted 1'.00" in Column concrete ,fixing of 12 gauge barbed wire galvd, 2 strands 4 points barbs. 9. Paint work (Emulsion on steel work and weather shield on wall both side). 10. Clearance & cleaning of site after the completion of work. 11. Supply and fixing of steel gate. Etc (Complete in all respect)	500.00	Rft		
			Total (Rs)		

TERMS & CONDITIONS.

1. The bidders are required to submit rate including all applicable taxes.
2. Interested suppliers/ Service Providers must have valid Tax Registration, complete business location with Phone, Fax & Postal address.
3. 2% of the total quoted price shall be submitted with bid as earnest money in the shape of DD/ PO or Bank Guarantee.
4. OGDCL reserves the right to accept or reject any Bid or to annul the Bidding process and reject all Bids as per PPRA rules.
5. Tender documents can be obtained from the office Regional Coordinator Sukkur.
6. Sealed Bids/ Quotations completed in all respect are to reach the address given below by 10:30 Hrs on **02.08.2017** which will be opened on the same day at 11:00 Hrs.

REGIONAL CORDINATOR
(REGIONAL OFFICE SUKKUR)
OIL & GAS DEVELOPMENT COMPANY LTD.
Bungalow A-25. Friends Society Shikar Pur road (Sukkur)
Contact# 0719310750/ 03005553517, Fax 071930749