

OIL & GAS DEVELOPMENT COMPANY LIMITED

SEISMIC PARTY NO-04

C/O Main Tcs Office Meri Colony Bannu Road, Near Old Pso Pump, KOHAT**Telephone # 051-9244343****Email: partychiefsp4@ogdcl.com****TENDER NOTICE**

1- Oil & Gas Development Company Limited (OGDCL) is the largest Exploration and Production listed Company of Pakistan having operations at 52 locations and fields in all the four provinces, intends to hire services for its operations. The details about the company can be obtained from website <http://www.ogdcl.com>

2- Sealed bids in duplicate are invited for the services given below under Competitive Bidding Procedure on Single Stage Two Envelope Bidding System. Terms and conditions are mentioned in the OGDCL master tender documents.

S.No.	Tender No.	Item Description and Specifications	Quantity	Bid Submission & Opening Date & Time
1	SP-4/WT/10038472/BOUNDARY WALL/2025/06	CONCRETE BOUNDARY WALL SIZE 8 RFT X 1 FT X 2 INCH ALONG WITH COLUMN 10 FT <ul style="list-style-type: none">✓ Wall Dimensions Reinforced Cement Concrete (RCC) boundary wall of 8 Running Feet (Rft) in length, 1 Foot (Ft) in width, and 2 Inches (In) in thickness.✓ Column Dimensions<ul style="list-style-type: none">○ RCC columns of 10 Ft height at suitable intervals,○ embedded properly in foundation for structural stability.✓ Concrete Grade<ul style="list-style-type: none">○ Minimum Grade M-20 (1:1.5:3 mix ratio) or as○ per Pakistan Standard Specifications○ for both wall and columns.✓ Reinforcement<ul style="list-style-type: none">○ High-strength deformed steel bars (Grade 60)○ used in columns and wall.○ Minimum 4 bars of 12mm dia for columns,○ tied with 8mm stirrups @ 6" c/c.✓ Foundation<ul style="list-style-type: none">○ Column foundation depth 2.5–3 Ft○ with a concrete footing base of 1.5 Ft x 1.5 Ft.✓ Formwork & Curing<ul style="list-style-type: none">○ Proper shuttering and formwork to○ ensure smooth finish.○ Minimum curing period: 7–10 days○ for wall and columns.✓ Plaster/Finishing<ul style="list-style-type: none">○ Both sides of the wall to be finished with○ 1:4 cement-sand plaster, ½ Inch thick.○ External face may be painted/treated with○ weather-resistant coating.	1750 RFT	15th SEPTEMBER 2025 11:00 AM

3- Tender Documents Tender Enquiry Can Be Obtained/Downloaded From OGDCL Website, [Www.Ogdcl.Com](http://www.Ogdcl.Com) Or On Written Request From The Office Of The Party Chief Seismic Party No.4 OGDCL C/O Manager Tcs Office Meri Colony Bannu Road, Near Old Pso Pump Kohat Kpk On Any Day From 0900 Hours (Pst) To 1300 Hours (Pst).

4- The Bids Will Be Received At The Office Of The Party Chief, Seismic Party No.4 Ogdcl, Near Ali Zai District Kohat Kpk On Time And Date Mentioned Against Tender Enquiry. Bidder(S) Or Their Authorized Representative(S) Are Encouraged To Attend The Tender Opening Meeting. The Dates For Opening Of The Financial Bids Against Tender Enquires Under Single Stage Two Envelope Bidding Procedures Will Be Communicated To The Technically Qualified & Financially Bidders Upon The Completion Of Technical Evaluation.

5- Bidders must provide their own business details at the time of tender purchase including Address, Phone & Fax Numbers and email (if any) for effective communication. If further details/clarifications are required, it may be obtained from Party Chief Office Seismic Party No-4 Ali-Zai Base Camp Hangu Road Kohat KPK via e-mail, phone, WhatsApp and personally.

6- The OGDCL reserves the right to accept or reject any bid and to annul the bidding process and reject all the bids at any time prior to award of Purchase Order.

Mailing Address:

PARTY CHIEF SEISMIC PARTY NO 4. OGDCL C/O MANAGER TCS OFFICE MERI COLONY BANNU ROAD, NEAR OLD PSO PUMP KOHAT KPK

Tel. Phone #: 051-9244343

Email: partychiefsp4@ogdcl.com